# KIMBALL UNION ACADEMY (KUA): KILTON AND WELCH BUILDINGS

MAY 15, 2023 PERMIT SET

THESE DRAWINGS ARE ONLY FOR THE KILTON AND WELCH BUILDINGS SITE WORK AND CIVIL DRAWINGS

FOR KILTON DORM RELATED DRAWINGS SEE "2023-05-15 PERMIT SET\_KILTON DORM" FOR WELCH DORM RELATED DRAWINGS SEE "2023-05-15 PERMIT SET\_WELCH DORM"



Locator Map / Aerial Photo (NOT TO SCALE)

#### PROJECT INFORMATION

#### Primary State Adopted Codes

NH State Building Code
ICC International Building Code (IBC) 2018 w/ NH Amendments

- ICC International Existing Building Code (IEBC) 2018 w/ NH Amendments
- ICC International
   ICC A117.1-2009
- ICC ATT7.1-2009
   ICC International Plumbing Code (IPC) 2018 w/ NH Amendments
- ICC International Mechanical Code (IMC) 2018 w/ NH Amendments
   ICC International Energy Conservation Code (IECC) 2018 w/ NH Amendments
- NFPA 70 Natrional Electric Code 2020 w/ NH Amendments

#### NH State Fire Code

- NFPA 1, Fire Code 2018
- NFPA 101, Life Safety Code 2018

\*When a conflict between codes is identified, IBC applies for all categories, or where one code or standard has a requirement and another code or standard does not have a requirement the code or standard with a requirement shall apply.

#### **USE AND OCCUPANCY CLASSIFICATION**

NFPA - 6.1.14.3.2 - Building Occupancy is a mixed combination of Assembly, Residential, and Storage. Building shall comply to most restrictive - **Assembly.** 

2,328 gsf

#### PROGRAM INFORMATION

KILTON:
20 new student beds
8 Renovated beds
2 new faculty residences

1 renovated faculty residence
Existing Dorm Area 2,644 gsf
Existing Faculty Residence 2,280 gsf
New Dorm Area 11,407 gsf
New Faculty Residence A 2,795 gsf

New Faculty Residence B WELCH:

19 new student beds
1 new faculty residence

1 renovated faculty residence
Existing Faculty Residence 2,704 gsf
New Dorm Area 10,735 gsf
New Faculty Residence A 2,776 gsf

#### TYPES OF CONSTRUCTION

IBC 2018 - Fire Resistance Ratings Requirements for building elements in a **Type VB** Building shall be:

Bearing Walls - Exterior 0 hours
Bearing Walls - Interior 0 hours
Floor - Ceiling assemblies - 0 hours
Roof - Ceiling assemblies - 0 hours
Interior non-bearing walls - 0 hours

Exterior non-bearing walls - 0 hours

Building shall equipped throughout with a type NFPA 13 automatic sprinkler system.

1 HR fire-rated separation at exit enclosures, mechanical & electrical rooms, & elevators.

5.86/200767:29W81CM Fire Egress Plans For All Common Path of Travel, Dead End Corridor, & Travel Distance Limits.

Note on Printing Drawings: Architectural demolition sheets and detail sheets depicting envelope control layers are to be printed in full color. Incorrect demolition work or control layer installation due to black & white prints shall be the responsibility of the Construction Manager to remedy. Said sheets are as follows, but not limited to:

AK-0.5, AK-1.0, AK-6.0, AK-6.1, AK-6.2, AK-6.3, AK-6.4, AK-6.5,
AK-6.6, AK-6.7, AK-6.8, AK-10.3, AND AK-10.6

AW-0.5, AW-1.0, AW-6.0, AW-6.1, AW-6.2, AW-6.3, AW-6.4,
AW-6.5, AW-6.6, AW-6.8, AW-10.3, AND AW-10.6

ADDITIONAL SHEETS TO BE PRINTED IN COLOR: A-0.0, A-0.1, AL-1.0, AL-1.1 AK-0.4, and AW-0.4

#### KILTON & WELCH CIVIL DRAWINGS NUMBER NAME C-0.1 SITE LEGEND & NOTES C-1.1 EXISTING CONDITIONS XXX C-2.1 SITE PLAN XXXX C-2.2 GRADING & DRAINAGE PLANS C-2.3 UTILITY PLAN C-2.4 EROSION CONTROL PLAN XX C-3.1 SEWER PLAN AND PROFILES 1 X C-3.2 SEWER PLAN AND PROFILES 2 C-4.1 SITE DETAILS C-4.2 SEWER DETAILS XX C-4.3 WATER DETAILS XX STORMWATER DETAILS C-4.4 XX X X EROSION CONTROL DETAILS C-4.5

NUMBER	NAME	BID PACKAGE 1	F 1 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4
E1	ELECTRICAL NOTES, LEGEND, DETAILS	X	>
E2	ELECTRICAL SITE PLAN	Х	>
E3	ELECTRICAL ONE LINE DIAGRAM	X	>
E4	ELECTRICAL LUMINAIRE SCHEDULE	Х	>
EK5	KILTON ELECTRICAL DEMOLITION	X	>
EK6	KILTON ELECTRICAL BASEMENT	X	>
EK7	KILTON LIGHTING FIRST FLOOR	X	>
EK8	KILTON LIGHTING SECOND FLOOR	X	>
EK9	KILTON POWER & SIGNAL FIRST FLOOR	Х	>
EK10	ELECTRICAL PANEL SCHEDULES	X	>
EW11	WELCH ELECTRICAL DEMOLITION	X	>
EW12	WELCH ELECTRICAL BASEMENT	X	>
EW13	WELCH ELECTRICAL FIRST FLOOR	X	>
EW14	WELCH ELECTRICAL SECOND FLOOR	X	>
EW15	ELECTRICAL PANEL SCHEDULES		>
E16	ELECTRICAL SCHEDULES		>
LV1	LOW VOLTAGE NOTES & DIAGRAM		>
LVK2	KILTON LOW VOLTAGE BASEMENT		>
LVK3	KILTON LOW VOLTAGE FIRST FLOOR		>
LVK4	KILTON LOW VOLTAGE SECOND FLOOR		>
LVW5	WELCH LOW VOLTAGE		>

KILTON & WELCH ARCHITECTURAL DRAWINGS						
NUMBER	NAME	SD SET	01/13/23 SET	BID PACKAGE #1 03/27/23	PERMIT SET 05/15/23	
A-0.0	COVER SHEET	X	Х	Х	Х	
A-0.1	LEGEND & ARCHITECTURAL INFORMATION			Χ	Χ	
A-0.2	TYPICAL ACCESSIBILITY DETAILS				X	
A-0.3	ARCHITECTURAL SITE PLAN	X	Х	Х	Х	
AL-1.0	LANDSCAPE PLAN			Х	Х	
AL-1.1	ENLARGED PLANTING PLANS & DETAILS			X	Х	

AK-4.2 FACULTY RESIDENCE ELEVATIONS

AN-3.0	BUILDING SECTIONS AT EXISTING			^	^
AK-5.1	BUILDING SECTIONS AT NEW	X	X	Χ	Χ
AK-5.2	BUILDING SECTIONS AT NEW			Χ	X
AK-5.3	BUILDING SECTIONS AT NEW			X	X
	EXTERIOR WALL SECTIONS AT EXISTING				X
AK-6.0				X	
AK-6.1	EXTERIOR WALL SECTIONS AT NEW			Χ	X
AK-6.2	EXTERIOR WALL SECTIONS AT NEW			X	X
AK-6.3	DETAILS			Χ	Χ
AK-6.4	DETAILS			Χ	Χ
AK-6.5	DETAILS			X	X
AK-6.6	DETAILS				X
AK-6.8	ROOF DETAILS			X	X
AK-6.10	INTERIOR DETAILS			X	X
AK-6.11	INTERIOR DETAILS				X
AK-7.1	ENLARGED COMMON AREA DRAWINGS				X
AK-7.1a	ENLARGED COMMON AREA ELEVATIONS				X
AK-7.2	ENLARGED PLANS & ELEVATIONS GEAR & KITCHEN				Χ
AK-7.3	ENLARGED PLANS & ELEVATIONS UPPER LOUNGE				X
AK-7.4	ENLARGED BATHROOM DRAWINGS				X
AK-7.5	ENLARGED BATHROOM DRAWINGS				X
AK-7.6	ENLARGED FACULTY RESIDENCE A DRAWINGS				X
AK-7.7	ENLARGED FACULTY RESIDENCE A DRAWINGS				X
AK-7.8	ENLARGED DORM ROOM DRAWINGS				X
				\ \/	
AK-8.1	DORM STAIR A DETAILS			X	X
AK-8.2	DORM STAIR B DETAILS			X	X
AK-8.3	FACULTY RESIDENCE STAIR DETAILS			Χ	X
AK-8.4	STAIR DETAILS			X	X
AK-8.5	ELEVATOR DRAWINGS				X
				X	
AK-9.1	MILLWORK				X
AK-10.1	INTERIOR FINISHES SCHEDULE			Χ	Χ
AK-10.1a	FLOOR FINISH PLANS				X
AK-10.14 AK-10.2	WINDOW SCHEDULE	X		X	X
AK-10.3	WINDOW DETAILS			X	X
AK-10.4	DOOR SCHEDULE			X	Χ
AK-10.5	DOOR SCHEDULE & DETAILS			X	Χ
AK-10.6	DOOR DETAILS			X	X
7 (10.0	DOOK DEI/ (IE)				
AW-0.4	FIRE EGRESS PLANS			X	X
AW-0.5	ASSEMBLY TYPES			X	X
AW-0.6	INTERIOR PARTITIONS			X	X
AW-1.0	EXISTING/DEMO PLANS	X	X	X	X
AW-2.1	BASEMENT PLAN	X	X	X	X
AW-2.2	FIRST FLOOR PLAN	X	X	X	X
AW-2.3	SECOND FLOOR PLAN			Χ	X
AW-2.4	FACULTY RESIDENCE PLANS			X	X
AW-2.5	ROOF PLAN			X	Χ
AW-3.1	BASEMENT RCP			X	X
AW-3.2	FIRST FLOOR RCP			X	X
AW-3.3	SECOND FLOOR RCP			X	X
AW-4.1	DORM ELEVATIONS	X	X	X	X
AW-4.2	FACULTY RESIDENCE ELEVATIONS	X	X	X	X
AW-5.0	BUILDING SECTIONS AT EXISTING			X	X
AW-5.1	BUILDING SECTIONS AT NEW	X	X	X	X
	BUILDING SECTIONS AT NEW		71		
AW-5.2				X	X
AW-5.3	BUILDING SECTIONS AT NEW			X	X
AW-6.0	EXTERIOR WALL SECTIONS AT EXISTING			X	X
AW-6.1	EXTERIOR WALL SECTIONS AT NEW			X	X
AW-6.2	EXTERIOR WALL SECTIONS AT NEW			X	X
AW-6.3	DETAILS			Χ	X
AW-6.4	DETAILS			Χ	Χ
AW-6.5	DETAILS			X	X
AW-6.6	DETAILS				X
AW-6.8	ROOF DETAILS			X	X
AW-6.10	INTERIOR DETAILS				X
AW-7.1	ENLARGED COMMON AREA DRAWINGS				X
AW-7.2	ENLARGED PLANS & ELEVATIONS GEAR & KITCHEN				X
AW-7.3	ENLARGED PLANS & ELEVATIONS				X
AW-7.4	ENLARGED BATHROOM DRAWINGS				X
AW-7.5	ENLARGED BATHROOM DRAWINGS				X
AW-7.6	FACULTY RES. ENLARGED PLANS AND ELEVATIONS				X
AW-7.7	ENLARGED FACULTY RESIDENCE DRAWINGS				X
AW-7.8	ENLARGED DORM ROOM DRAWINGS				X
AW-8.1	DORM NORTH STAIR SECTIONS			X	Χ
AW-8.2	DORM SOUTH STAIR SECTIONS			X	X
AW-8.3	ALL FACULTY RESIDENCES STAIR SECTIONS				
				X	X
AW-8.4	STAIR DETAILS				X
AW-8.5	ELEVATOR DRAWINGS			Χ	Χ
AW-9.1	MILLWORK				X
AW-10.1				V	
	INTERIOR FINISHES SCHEDULE			X	X
W-10.1a	FLOOR FINISH PLANS				X
AW-10.2	WINDOW SCHEDULE	X		Χ	X
AW-10.3	WINDOW DETAILS			Χ	X
AW-10.4	DOOR SCHEDULE			X	X
111110.4	DOOK JUILDULL			^	$\wedge$

AW-10.5 DOOR SCHEDULE & DETAILS

number	NAME	SD SET	BID PACKAGE #1	
SK-0.1	GENERAL NOTES, BASIS OF DESIGN		X	
SK-0.1	GENERAL NOTES		X	
SK-0.3	SPECIAL INSPECTIONS		X	H
SK-1.0	FOUNDATION PLAN		X	H
SK-1.1	FIRST FLOOR FRAMING PLAN		X	
SK-1.2	SECOND FLOOR FRAMING PLAN		X	
SK-1.3	ROOF FRAMING PLAN		X	
SK-1.4	FACULTY RESIDENCE 'A' PLANS		X	
SK-2.0	TYPICAL FOUNDATION DETAILS		X	Ī
SK-2.1	FOUNDATION DETAILS		X	T
SK-3.0	TYPICAL FRAMING DETAILS		X	T
SK-3.1	FRAMING DETAILS		X	Ī
SK-3.2	FRAMING DETAILS		X	П
SK-3.3	TYPICAL TRUSS DETAILS		X	ı
SK-3.4	TYPICAL SHEAR WALL DETAILS		Χ	
SW-0.1	GENERAL NOTES, BASIS OF DESIGN		X	
SW-0.2	GENERAL NOTES		X	
SW-0.3	SPECIAL INSPECTIONS		X	
SW-1.0	FOUNDATION PLAN		X	
SW-1.1	FIRST FLOOR FRAMING PLAN		X	
SW-1.2	SECOND FLOOR FRAMING PLAN		X	
SW-1.3	ROOF FRAMING PLAN		X	
SW-2.0	TYPICAL FOUNDATION DETAILS		X	
SW-2.1	FOUNDATION DETAILS		X	
SW-3.0	TYPICAL FRAMING DETAILS		X	
SW-3.1	FRAMING DETAILS		X	
SW-3.2	FRAMING DETAILS		X	
SW-3.3	TYPICAL TRUSS DETAILS		X	
SW-3.4	TYPICAL SHEAR WALL DETAILS		X	

	KILTON & WELCH MECHANICAL DRAWING	S	
number	NAME	BID PACKAGE 1	PERMIT SET
MK-1.1	KILTON BASEMENT - AIR DISTRIBUTION	X	X
MK-1.2	KILTON FIRST FLOOR - AIR DISTRIBUTION	X	X
MK-1.3	KILTON SECOND FLOOR - AIR DISTRIBUTION	X	X
MK-2.1	KILTON BASEMENT - MECHANICAL PIPING	X	X
MK-2.2	KILTON FIRST FLOOR - MECHANICAL PIPING	X	X
MK-2.3	KILTON SECOND FLOOR - MECHANICAL PIPING	X	X
MK-3.1	MECHANICAL DETAILS	X	X
MK-3.2	MECHANICAL DETAILS	X	X
MK-3.3	MECHANICAL DETAILS	X	X
MK-4.1	MECHANICAL SCHEDULES	X	X
MK-4.2	MECHANICAL SCHEDULES	X	Χ
MW-1.1	WELCH BASEMENT - AIR DISTRIBUTION	X	X
MW-1.2	WELCH FIRST FLOOR - AIR DISTRIBUTION	X	X
MW-1.3	WELCH SECOND FLOOR - AIR DISTRIBUTION	X	X
MW-2.1	WELCH BASEMENT - MECHANICAL PIPING	X	X
MW-2.2	WELCH FIRST FLOOR - MECHANICAL PIPING	X	X
MW-2.3	WELCH SECOND FLOOR - MECHANICAL PIPING	X	X
MW-3.1	MECHANICAL DETAILS	X	X
MW-3.2	MECHANICAL DETAILS	X	X
MW-3.3	MECHANICAL DETAILS	X	X
MW-4.01	MECHANICAL SCHEDULES		Χ
MW-4.02	MECHANICAL SCHEDULES		Χ

KILTON & WELCH PLUMBING DRAWINGS					
NUMBER	NAME	BID PACKAGE 1	PERMIT SET		
PK-1.1	KILTON BASEMENT - WASTE & VENT	X	X		
PK-1.2	KILTON FIRST FLOOR - WASTE & VENT	X	Χ		
PK-1.3	KILTON SECOND FLOOR - WASTE & VENT	X	X		
PK-2.1	KILTON BASEMENT - DOMESTIC WATER	X	Χ		
PK-2.2	KILTON FIRST FLOOR - DOMESTIC WATER	X	Χ		
PK-2.3	KILTON SECOND FLOOR - DOMESTIC WATER	X	Χ		
PK-3.1	KILTON BASEMENT - CONDENSATE	X	Χ		
PK-3.3	KILTON SECOND FLOOR - CONDENSATE	X	Χ		
PK-4.1	KILTON - PLUMBING DETAILS		Χ		
PK-4.2	KILTON - PLUMBING SCHEDULES		X		
PW-1.1	WELCH BASEMENT & FIRST FLOOR - WASTE & VENT	X	X		
PW-1.2	WELCH SECOND FLOOR - WASTE & VENT	X	X		
PW-2.1	WELCH BASEMENT & FIRST FLOOR - DOMESTIC WATER	X	Χ		
PW-2.2	WELCH SECOND FLOOR - DOMESTIC WATER	X	Χ		
PW-3.1	WELCH BASEMENT & FIRST FLOOR - CONDENSATE	X	X		
PW-3.2	WELCH SECOND FLOOR - CONDENSATE		X		
PW-4.1	WELCH - PLUMBING DETAILS		Χ		
PW-4.2	WELCH - PLUMBING SCHEDULES		X		



ANDREA MURRAY, AIA, NCARB, LEED AP andrea@vermontintegratedarchitecture.com

ASHAR NELSON, AIA, LEED AP ashar@vermontintegratedarchitecture.com

P.O. Box 862 Middlebury, VT 05753 802.989.7249

CIVIL ENGINEER

Nicholas Fiore, P.E
Engineering Ventures
nikf@engineeringventures.com
802.863.6225

STRUCTURAL ENGINEER

Bob Neeld, P.E Engineering Ventures bobn@engineeringventures.com 802.863.6225

MECH./PLUMBING ENGINEER

Daniel Dupras, P.E.
Engineering Services of Vermont, LLC
daniel.dupras@esvtllc.com
802.885.8091

ELECTRICAL ENGINEER

Claus Bartenstein, P.E., LEED-AP
Engineering Services of Vermont, LLC
claus.bartenstein@esvtllc.com
802.885.8091

CONSTRUCTION MANAGER

Calvin Russell, Senior Project Manager
ReArch Company, Inc.
calvinr@rearchcompany.com

802.863.8727



DATE ISSUED: 05/15/23 Drawn: JG Checked: SR

# Date Description

**REVISIONS:** 


PERMIT SET 05/15/2023

KUA
KILTON/WELCH
DORMITORIES

Main Street, Meriden, NH 03770

**COVER SHEET** 

A-0.0





ASHAR NELSON, AIA, LEED AP ashar@vermontintegratedarchitecture.com

P.O. Box 862 Middlebury, VT 05753 802.989.7249

CIVIL ENGINEER

Nicholas Fiore, P.E Engineering Ventures nikf@engineeringventures.com 802.863.6225

STRUCTURAL ENGINEER

Bob Neeld, P.E Engineering Ventures bobn@engineeringventures.com 802.863.6225

MECH./PLUMBING ENGINEER

Daniel Dupras, P.E.
Engineering Services of Vermont, LLC
daniel.dupras@esvtllc.com
802.885.8091

ELECTRICAL ENGINEER

Claus Bartenstein, P.E., LEED-AP
Engineering Services of Vermont, LLC
claus.bartenstein@esvtllc.com

802.885.8091

802.863.8727

CONSTRUCTION MANAGER

Calvin Russell, Senior Project Manager
ReArch Company, Inc.

calvinr@rearchcompany.com



DATE ISSUED: 05/15/23 Drawn: SR Checked: SR

revisions:

# Date Description


PERMIT SET 05/15/2023

KUA
KILTON/WELCH
DORMITORIES

Main Street, Meriden, NH 03770


ARCHITECTURAL SITE PLAN

A-0.3




Description

PLANTING SCHEDULE					
TAG	COMMON NAME	BOTANICAL NAME	MATURE SIZE		
P1	SHASTA DAISY 'SNOW CAP'	LEUCANTHEUM SUPERBUM	18-24" HIGH		
P2	BEE BALM 'PARDON MY CERISE'	MONDARDA DIDYMA	14-18" HIGH		
P3	PURPLELEAF WINTERCREEPER	EUNONYMOUS FORTUNEI			
R1	CINNAMON FERN	OSMUNDASTRUM CINNAMOMEUM	6' TALL		
R2	TUSSOCK SEDGE	CAREX STRICTA	3' TALL x 2' WIDE		
R3	BLUE SEDGE	CAREX FLACCA	8-10" TALL x 18" WIDE		
<b>S</b> 1	RHODODENDRON 'PJM WHITE FORM'	RHODODENDRON PJM WHITE FORM	3-6' TALL x 3'6' WIDE		
S2	FOTHERGILLA	FOTHERGILLA GARDENII	3' TALL x 3' WIDE		
S3	WINTERBERRY	ILEX VERTICILLATA	3' TALL x 3' WIDE		
S4	EMERALD GREEN ARBORVITAE	THUIA OCCIDENTALIS	12' TALL x 4' WIDE		
T1	RED MAPLE	ACER RUBRUM	50' TALL x 20' WIDE		
T2	TREE LILAC	SYRINGA RETICULATA	30' TALL x 25' WIDE		
T3	FLOWERING CRABAPPLE	MALUS 'PRAIRIFIRE'	25' TALL x 25' WIDE		



2 Plaza & Rain Gardens Enlarged Plan
1" = 10'-0"





ASHAR NELSON, AIA, LEED AP ashar@vermontintegratedarchitecture.com

P.O. Box 862 Middlebury, VT 05753 802.989.7249

CIVIL ENGINEER

Nicholas Fiore, P.E
Engineering Ventures
nikf@engineeringventures.com
802.863.6225

STRUCTURAL ENGINEER

Bob Neeld, P.E Engineering Ventures bobn@engineeringventures.com 802.863.6225

MECH./PLUMBING ENGINEER

Daniel Dupras, P.E. Engineering Services of Vermont, LLC daniel.dupras@esvtllc.com 802.885.8091

ELECTRICAL ENGINEER

Claus Bartenstein, P.E., LEED-AP
Engineering Services of Vermont, LLC
claus.bartenstein@esvtllc.com
802.885.8091

CONSTRUCTION MANAGER
Calvin Russell, Senior Project Manager
ReArch Company, Inc.
calvinr@rearchcompany.com
802.863.8727



DATE ISSUED: 05/15/23 Drawn: SC Checked: SR

REVISIONS:

# Date Description

PERMIT SET 05/15/2023

KUA KILTON/WELCH DORMITORIES

Main Street, Meriden, NH 03770

ENLARGED
PLANTING PLANS
& DETAILS

AL-1.1

### STANDARD ABBREVIATIONS

OTTAIND TAIL	חוטט	7 17 (110110					
BENCHMARK	ВМ	END OF VERTICAL CURVE ELEVATION	EVCE	LIMITS OF CONSTRUCTION	LOC	REINFORCED CONCRETE PIPE	RCP
BEGINNING OF VERTICAL CURVE ELEVATION	BVCE	END OF VERTICAL CURVE	EVCE	LIMITS OF DISTURBANCE	LOD	RIGHT-OF-WAY	ROW
	BVCE	STATION	EVCS	MAXIMUM	MAX	SANITARY	SAN
BEGINNING OF VERTICAL CURVE STATION	BVCS	EXISTING	EX	MINIMUM	MIN	SANITARY MANHOLE	SMH
CAST-IN-PLACE	CIP	EXISTING GRADE/GROUND	EG	MANUAL ON UNIFORM	MUTOD	SEPTIC TANK	ST
CAST IRON	CI	FINISHED FLOOR	FF	TRAFFIC CONTROL DEVICES	MUTCD	SILT FENCE	SF
CATCH BASIN	СВ	FINISHED GRADE/GROUND	FG	MONITORING WELL	MW	SLOPE	S=
CENTERLINE	<b>©</b>	FIELD INLET	FI	MONUMENT	MON	STATION	STA
CLEAN OUT	C/0	FLARED END SECTION	FES	NOT IN CONTRACT	NIC	STORM MANHOLE	DMH
CORRUGATED METAL PIPE	СМР	FOOT, FEET	FT	NOT TO SCALE	NTS	TANGENT	TAN
CUBIC FEET	CF	FOOTING	FTG	POINT OF CURVATURE	PC	TANGENT TO CURVE	TC
CUBIC FEET PER SECOND	CFS	FOUNDATION	FND	POINT OF INTERSECTION	PI	TAPPING SLEEVE AND VALVE	TS&V
CUBIC YARD	CY	GALLONS PER MINUTE	GPM	POLYETHYLENE, PROFESSIONAL ENGINEER	PE	TEMPORARY BENCHMARK	TBM
DIAMETER	DIA	GATE VALVE	GV	PROPERTY LINE	PL	TEST PIT	TP
DISTRIBUTION BOX	D-BOX	HEADWALL	HW	PERC TEST, POINT OF TANGENCY		TOP OF BANK	TOB
DUCTILE IRON	DI	HIGH DENSITY POLYETHYLENE	HDPE	POLYVINYL CHLORIDE	PVC	TOP OF CURB	TOC
EDGE OF CONCRETE	EOC	HYDRANT	HYD	POINT OF VERTICAL INTERSECTION	PVI	TOP OF WALL	TOW
EDGE OF GRAVEL	EOG	INTERSECTION	INT	POND	PND	TYPICAL	TYP
EDGE OF PAVEMENT	EOP	INVERT	INV	QUANTITY	QTY	VERIFY IN FIELD	VIF
ELECTRIC	ELEC	IRON PIN	IP	QUALITY ASSURANCE	QA	WATER VALVE	w
ELECTRIC MANHOLE	ЕМН	IRON PIPE SIZE	IPS	QUALITY CONTROL	QC		
		<u> </u>		<u> </u>	~~		

RADIUS

#### GENERAL NOTES

LENGTH

ELEVATION

- 1. EXACT OBJECT LOCATIONS MAY DIFFER FROM THAT AS SHOWN, AND ADDITIONAL SUB-SURFACE AND SURFACE UTILITIES AND STRUCTURES MAY EXIST. THE CONTRACTOR IS TO PROCEED WITH GREAT CARE IN EXECUTING ANY WORK
- 2. UTILITIES SHOWN DO NOT PURPORT TO CONSTITUTE OR REPRESENT ALL UTILITIES LOCATED UPON OR ADJACENT TO THE SURVEYED PREMISES. EXITING UTILITY LOCATIONS ARE APPROXIMATE ONLY. THE CONTRACTOR SHALL FIELD VERIFY ALL UTILITIES. ALL DISCREPANCIES SHALL BE REPORTED TO THE OWNER AND ENGINEER. SITE CONTRACTOR SHALL CALL UTILITY LOCATOR SERVICE AND UTILITY OWNERS 72 HOURS, EXCLUSIVE OF WEEKENDS AND HOLIDAYS, PRIOR TO ANY DIGGING, DRILLING, OR BLASTING: A. DIG SAFE (TEL: #811)
- B. NON DIG SAFE MEMBÉR FACILITY OPERATORS IF KNOW. A LIST OF DIG SAFE MEMBERS BY STATE CAN BE FOUND ON THE DIG SAFE WEB SITE WWW.DIGSAFE.COM
- 3. THE ENGINEER SHALL BE NOTIFIED IN WRITING OF ANY CONDITIONS THAT VARY FROM THOSE SHOWN ON THE PLANS. THE CONTRACTOR'S WORK SHALL NOT VARY FROM THE PLANS WITHOUT THE EXPRESSED APPROVAL FROM THE ENGINEER.
- 4. THE CONTRACTOR IS INSTRUCTED TO COOPERATE WITH ANY AND ALL OTHER CONTRACTORS PERFORMING WORK ON THIS JOB SITE DURING THE PERFORMANCE OF THIS CONTRACT.
- 5. THE CONTRACTOR SHALL RESTORE LAWNS, DRIVEWAYS, CULVERTS, SIGNS AND OTHER PUBLIC OR PRIVATE PROPERTY DAMAGED OR REMOVED TO EXISTING CONDITIONS OR BETTER AS DETERMINED BY THE ENGINEER. ANY DAMAGED TREES, SHRUBS AND/OR HEDGES SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE, UNLESS NOTED OTHERWISE.
- 6. THE CONTRACTOR SHALL COMPLY WITH ALL REQUIRED PERMITS.
- 7. THE OWNER SHALL BE RESPONSIBLE FOR OBTAINING, AND INCURRING THE COST OF ALL REQUIRED PERMITS, INSPECTIONS, AND CERTIFICATES.
- 8. THE CONTRACTOR WILL PROTECT EXISTING PROPERTY LINE MONUMENTATION. ANY MONUMENTATION DISTURBED OR DESTROYED, AS JUDGED BY THE ENGINEER OR OWNER SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE UNDER THE SUPERVISION OF A NEW HAMPSHIRE STATE LICENSED LAND SURVEYOR.
- 9. IT IS THE CONTRACTOR'S RESPONSIBILITY TO EXAMINE ALL PLAN SHEETS AND SPECIFICATIONS, AND COORDINATE WORK WITH ALL CONTRACTS FOR THE SITE.
- 10. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONDUCT EXPLORATORY TEST PITS AS MAY BE REQUIRED TO DETERMINE UNDERGROUND CONDITIONS.
- 11. ALL TRENCH EXCAVATION AND ANY REQUIRED SHEETING AND SHORING SHALL BE DONE IN ACCORDANCE WITH THE LATEST OSHA REGULATIONS FOR CONSTRUCTION.
- 12. CONTRACTOR SHALL BE RESPONSIBLE FOR DEWATERING AND THE MAINTENANCE OF SURFACE DRAINAGE DURING THE COURSE OF WORK.
- 13. MAINTAIN FLOW FOR ALL EXISTING UTILITIES, UNLESS NOTED OTHERWISE.
- 14. ALL SITE FILL SHALL MEET SELECTED FILL STANDARDS UNLESS NOTED OTHERWISE ON THE DRAWINGS.
- 15. CONTRACTOR TO GRADE ALL AREAS ON THE SITE TO PROVIDE POSITIVE DRAINAGE AWAY FROM BUILDINGS AND IMPERVIOUS SURFACES.
- 16. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ALL FIELD LAYOUT. THE CONTRACTOR SHALL PROVIDE MARKED—UP AS—BUILT PLANS FOR ALL UTILITIES SHOWING CONNECTIONS, BENDS, VALVES, LENGTHS OF LINES AND INVERTS. AS—BUILT PLANS SHALL BE REVIEWED BY THE OWNER AND HIS REPRESENTATIVES BEFORE UTILITIES WILL BE ACCEPTED.
- 17. CONTRACTOR SHALL BE RESPONSIBLE FOR PROPER INSTALLATION, MONITORING, MAINTENANCE AND REMOVAL OF ALL TEMPORARY EROSION CONTROL MEASURES AND TAKING PRECAUTIONARY STEPS TO AVOID ANY SEDIMENT TRANSFER TO NEIGHBORING SITES OR WATERS OF THE STATE.

## SYMBOL LEGEND

JINDOL	LLOLND		
PROPOSED FEATURES		EXISTING FEATURES	
•	BOUND	•	BOUND
•	BENCHMARK	<b>+</b>	BENCHMARK
•	DRILL HOLE	•	DRILL HOLE
A	SURVEY POINT	$\triangle$	SURVEY POINT
•	IRON PIN	0	IRON PIN
TP1 <b>⊞</b>	TEST PIT	<i>TP1</i> <b>■</b>	TEST PIT
<b>■</b> J B1	1231 111	B1	ILOI III
•	BORING	•	BORING
P1 <del>C</del>	PERC TEST	<i>P1</i>	PERC TEST
	CATCH BASIN (SQUARE)		CATCH BASIN (SQUARE)
•••• •	CATCH BASIN (ROUND)	<u></u>	CATCH BASIN (ROUND)
$\Leftrightarrow$	HEADWALL	$\Leftrightarrow$	HEADWALL
$\stackrel{\smile}{\sim}$	FLARED END SECTION	ightharpoonup	FLARED END SECTION
	STONE APRON		STONE APRON
<b>D</b>	DRAIN MANHOLE (DMH)	<b>(1)</b>	DRAIN MANHOLE (DMH)
o c/o	DRAINAGE CLEAN OUT	o c/o	DRAINAGE CLEAN OUT
<b>\$</b>	SANITARY SEWER MANHOLE (SMH)	<b>S</b>	SANITARY SEWER MANHOLE (SMH,
o c/0	SANITARY CLEAN OUT	o C/O	SANITARY CLEAN OUT
<b>X</b>	HYDRANT	₩ W X	HYDRANT
	WATER SHUTOFF	WV WV	WATER SHUTOFF
GV	TAPPING SLEEVE & VALVE	GV	TAPPING SLEEVE & VALVE
$\bowtie$	GATE VALVE	$\bowtie$	GATE VALVE
W	WELL	<b>(W)</b>	WELL
Ф	UTILITY POLE	O	UTILITY POLE
-•	GUY POLE	-•	GUY POLE
<b>®</b>	ELECTRICAL MANHOLE	E	ELECTRICAL MANHOLE
н	BUILDING MOUNTED LIGHT	•	FLOOD LIGHT
<b>®•</b>	LIGHT POST	$\Rightarrow$	LIGHT POST
•	TELEPHONE MANHOLE	1	TELEPHONE MANHOLE
<b>©</b>	NATURAL GAS MANHOLE	<b>©</b>	NATURAL GAS MANHOLE
©	COMMUNICATION MANHOLE	©	COMMUNICATION MANHOLE
•	BOLLARD		BOLLARD
<del>- o -</del>	SINGLE POLE SIGN	<del></del> 0-	SINGLE POLE SIGN
<del>- 0 0 -</del>	DOUBLE POLE SIGN	-0-0	DOUBLE POLE SIGN
+100.5	SPOT ELEVATION	+ 100.00	SPOT ELEVATION
<b>ራ</b>	ACCESSIBLE PARKING STALL	Ġ	ACCESSIBLE PARKING STALL
$\Rightarrow$	DRAINAGE FLOW	$\Rightarrow$	DRAINAGE FLOW
$(\cdot)(\cdot)(\cdot)$	DECIDUOUS TREE		DECIDUOUS TREE
× × × × × × × × × × × × × × × × × × ×	CONIFEROUS TREE		CONIFEROUS TREE

#### SURVEY NOTES

- 1. TOPOGRAPHIC AND PHYSICAL FEATURES TAKEN FROM A FIELD SURVEY PREPARED BY DIBERNARDO ASSOCIATES ON DECEMBER 15, 2022.
- 2. THE VERTICAL DATUM IS NAVD 1988. THE HORIZONTAL DATUM IS THE NEW HAMPSHIRE STATE PLANE
- COORDINATE SYSTEM.
- 3. NORTH ORIENTATION IS REFERENCED TO APPROXIMATE NEW HAMPSHIRE GRID NORTH DERIVED FROM GPS READINGS OBSERVED BY OTHERS.
- 4. UTILITIES SHOWN DO NOT PURPORT TO CONSTITUTE OR REPRESENT ALL UTILITIES LOCATED UPON OR ADJACENT TO THE SURVEYED PREMISES.
- 5. EXISTING UTILITIES SHOWN ON PLANS WERE TAKEN FROM FIELD OBSERVATIONS OF VISIBLE UTILITIES. CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFYING UTILITY LOCATIONS PRIOR TO COMMENCING WORK. NOTIFY ENGINEER OF ANY DISCREPANCY BETWEEN UTILITIES AS SHOWN AND AS FOUND. THE CONTRACTOR SHALL CONTACT DIG SAFE (811 or 888–344–7233) A MINIMUM OF 72 HOURS, EXCLUSIVE OF SATURDAYS, SUNDAYS, AND LEGAL HOLIDAYS, PRIOR TO ANY CONSTRUCTION.

#### WILDLIFE PROTECTION NOTES

- 1. ALL OBSERVATIONS OF THREATENED OR ENDANGERED SPECIES <u>SHALL BE REPORTED IMMEDIATELY</u> TO THE NEW HAMPSHIRE FISH AND GAME DEPARTMENT NONGAME AND ENDANGERED WILDLIFE ENVIRONMENTAL REVIEW PROGRAM BY PHONE AT 603-271-2461 AND BY EMAIL AT NHFGREVIEW@WILDLIFE.NH.GOV. EMAIL SUBJECT LINE: NHB23-0576, KUA KILTON/WELCH DORMATORIES, WILDLIFE SPECIES OBSERVATION.
- 2. PHOTOGRAPHS OF THE OBSERVED SPECIES AND NEARBY ELEMENTS OF HABITAT OR AREAS OF LAND DISTURBANCE SHALL BE PROVIDED TO NHF&G IN DIGITAL FORMAT AT THE ABOVE EMAIL ADDRESS FOR VERIFICATION AS FEASIBLE;
- 3. IN THE EVENT A THREATENED OR ENDANGERED SPECIES IS OBSERVED ON THE PROJECT SITE DURING THE TERM OF THE PERMIT, THE SPECIES SHALL NOT BE DISTURBED, HANDLED, OR HARMED IN ANY WAY PRIOR TO CONSULTATION WITH NHF&G AND IMPLEMENTATION OF CORRECTIVE ACTIONS RECOMMENDED BY NHF&G, IF ANY, TO ASSURE THE PROJECT DOES NOT APPRECIABLY JEOPARDIZE THE CONTINUED EXISTENCE OF THREATENED AND ENDANGERED SPECIES AS DEFINED IN FIS 1002.04
- 4. THE NHF&G, INCLUDING ITS EMPLOYEES AND AUTHORIZED AGENTS, SHALL HAVE ACCESS TO THE PROPERTY DURING THE TERM OF THE PERMIT.

#### LINETYPE LEGEND

PROPOSED FEATURES		EXISTING FEATURES	
100	— MAJOR CONTOUR	- <i>-</i>	- MAJOR CONTOUR
98 —	- MINOR CONTOUR	<i>98</i>	- MINOR CONTOUR
· · ·	— EDGE OF RIVER		- EDGE OF RIVER
	— EDGE OF POND		EDGE OF POND
	EDGE OF POND		
			• FLOOD PLAIN
	- PROPERTY LINE		PROPERTY LINE
	- RIGHT OF WAY		- RIGHT OF WAY
·	— SETBACK		- SETBACK
	— EASEMENT	<u> </u>	- EASEMENT
	— LIMIT OF CONSTRUCTION		LIMIT OF CONSTRUCTION
LOD	— LIMIT OF DISTURBANCE		LIMIT OF DISTURBANCE
SF	— SILT FENCE		SILT FENCE
1 · 1 · 1 · 1 · 1 · 1 · 1 · 1 · 1 · 1 ·			DEMOLITION WORK
	— CENTERLINE		- CENTERLINE
	— EDGE OF PAVEMENT		- EDGE OF PAVEMENT
	— EDGE OF GRAVEL		- EDGE OF GRAVEL
	— EDGE OF CONCRETE		EDGE OF CONCRETE
	— CURB		- CURB
x x	— EENICE (DARDED WIDE)	X X	- FENCE (DADDEN WIDE)
	,		
	— FENCE (CHAIN LINK)		FENCE (CHAIN LINK)
	— FENCE (WOODEN)		- FENCE (WOODEN)
o o o o	⊸。GUARD RAIL	. 0 0 0 0 0 0	。 GUARD RAIL
$\bigcirc \bigcirc $	\ . TREE LINE		TREE LINE
			- EDGE OF WETLANDS — DELINEATEL
		· · · · · · · · · · · · · · · · · · ·	- EDGE OF WETLANDS — APPROXIMA
·	STONE WALL		
s	SANITARY SEWER		SANITARY SEWER
		(S)	SANITARY SEWER APPROX.
FM	SEWER FORCEMAIN	FM	SEWER FORCEMAIN
ss	SEWER SERVICE	SS	SEWER SERVICE
	DISPOSAL AREA LATERAL	SLA	- DISPOSAL ARFA LATFRAL
SD		SD	
SD	STORM LINE		
		(SD)	
UD	UNDER DRAIN	UD	UNDER DRAIN
FD	FOUNDATION DRAIN	————FD ———	- FOUNDATION DRAIN
RD	ROOF DRAIN	RD	ROOF DRAIN
<del></del>	— DITCH/SWALE	<b>→</b> · · <b>→</b> · · · <b>→</b>	- DITCH/SWALF
т_		т_	,
I	TELECOMM		
		(T)	
UGT	UNDERGROUND TELECOMM	UGT	_ UNDERGROUND TELECOMM
OHT	OVERHEAD TELECOMM	OHT	OVERHEAD TELECOMM
E	ELECTRIC LINE	——————————————————————————————————————	- ELECTRIC LINE
		(E)	- FLECTRIC APPROX.
	UNDERGROUND ELECTRIC		
	OVERHEAD ELECTRIC	OHE	
SL	ELECTRICAL SITE LIGHTING		- ELECTRICAL SITE LIGHTING
W	WATER LINE		- WATER LINE
		(W)	- WATER APPROX.
\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	WATER SERVICE		
		GAS	
GAS	— UAS LINE		
		——(G)—	
CATV———	CABLE TV	CATV	- CABLE TV
UGTV-	UNDERGROUND CABLE TV	OHTV	UNDERGROUND CABLE TV
UGTV	OVERHEAD CABLE TV	OHTV	OVERHEAD CABLE TV
	STEAM LINE	STM	
<b>5</b>			
LPS——	LOW PRESSURE STEAM	<del>-</del>	LOW PRESSURE STEAM
	HIGH PRESSURE STEAM	HPS	- HIGH PRESSURE STEAM
HPS-			
	HOT WATER	HW	- HOT WATER



ANDREA MURRAY, AIA, NCARB, LEED AP andrea@vermontintegratedarchitecture.com

ASHAR NELSON, AIA, LEED AP ashar@vermontintegratedarchitecture.com

P.O. Box 862 Middlebury, VT 05753 802.989.7249

CIVIL ENGINEER
Nicholas A. Fiore, P.E
Engineering Ventures
nikf@engineeringventures.com
802.863.6225

STRUCTURAL ENGINEER

Bob Neeld, P.E, President
Engineering Ventures
bobn@engineeringventures.com
802.863.6225

MECH./PLUMBING ENGINEER
Daniel Dupras, P.E.
Engineering Services of Vermont, LLC
daniel.dupras@esvtllc.com
802.885.8091

ELECTRICAL ENGINEER

Claus Bartenstein, P.E., LEED-AP
Engineering Services of Vermont, LLC
claus.bartenstein@esvtllc.com
802.885.8091

CONSTRUCTION MANAGER
Calvin Russell, Senior Project Manager
ReArch Company, Inc.
calvinr@rearchcompany.com
802.863.8727

DATE ISSUED: 03/27/2023 Drawn: EV

REVISIONS:
# Date Description

Checked: NAF




PERMIT SET 05/15/2023

#### KUA KILTON/WELCH DORMITORIES

Main Street, Meriden, NH 03770

SITE LEGEND AND NOTES

C0.1





ASHAR NELSON, AIA, LEED AP ashar@vermontintegratedarchitecture.com

P.O. Box 862 Middlebury, VT 05753 802.989.7249

CIVIL ENGINEER

Nicholas A. Fiore, P.E
Engineering Ventures
nikf@engineeringventures.com
802.863.6225

STRUCTURAL ENGINEER

Bob Neeld, P.E, President
Engineering Ventures
bobn@engineeringventures.com
802.863.6225

MECH./PLUMBING ENGINEER

Daniel Dupras, P.E.
Engineering Services of Vermont, LLC
daniel.dupras@esvtllc.com
802.885.8091

ELECTRICAL ENGINEER

Claus Bartenstein, P.E., LEED-AP
Engineering Services of Vermont, LLC
claus.bartenstein@esvtllc.com
802.885.8091

CONSTRUCTION MANAGER
Calvin Russell, Senior Project Manager
ReArch Company, Inc.
calvinr@rearchcompany.com
802.863.8727

DATE ISSUED: 03/31/2023 Drawn: EV Checked: NAF


REVISIONS:

NICHOLAS FIORE

No. 13286

PERMIT SET 05/15/2023

# Date Description



+ <u>SMH2</u> RIM EL.=947.43'

MACLEAY

BUILDING

IN 8" PVC=939.54"

OUT 8" PVC=939.51'

- 1) United States Department of Agriculture, Natural Resources Conservation Service. 2018. Field Indicators of Hydric Soils in the United States, Version 8.2. L.M. Vasilas, G.W. Hurt, and J.F. Berkowitz (eds.). USDA, NRCS, in cooperation with the National Technical Committee for Hydric Soils.
- 2) Field Indicators for Identifying Hydric Soils In New England. Version 4. April 2019. New England Hydric Soils Technical Committee.
- 3) U.S. Army Corps of Engineers 2020: National Wetland Plant List, version 3.5

  (http://wetland\_plants.usace.army.mil). U.S. Army Corps of Engineers, Engineer
  Research and Development Center, Cold Regions Research and Engineering Laboratory,
  Hanover, NH.
- 4) The National Wetland Plant List: 2016 wetland ratings. Lichvar, R.W., D.L. Banks, W.N. Kirchner, and N.C. Melvin. 2016. Phytoneuron 2016-30: 1-17. Published 28 April 2016. ISSN 2153 733X
- 5) Corps of Engineers Wetlands Delineation Manual. January 1987. Wetlands Research Program Technical Report Y-87-1.
- Regional Supplement to the Corps of Engineers Wetland Delineation Manual:
  Northcentral and Northeast Region. January 2012, Version 2. U.S. Army Corps of Engineers. Environmental Laboratory ERDC/EL TR-12-1.
- Classification of Wetlands and Deepwater Habitats of the United States. December 1979. L. Cowardin, V. Carter, F. Golet, and E. LaRoe. US Department of the Interior. Fish and Wildlife Service. FWS/OBS-79/31.

Stoney Ridge Environmental LLC.

8 Kiana Road, Alton, NH 03809

(p): 603-776-5825, (f) 603-776-5826, info@stoneyridgeenv.com

GRAPHIC SCALE

1 inch = 20 ft.for sheet size 24" x 36" KILTON/WELCH
DORMITORIES


Main Street,

Meriden, NH 03770

KUA

EXISTING CONDITIONS

C1.1





ASHAR NELSON, AIA, LEED AP ashar@vermontintegratedarchitecture.com

P.O. Box 862 Middlebury, VT 05753 802.989.7249

CIVIL ENGINEER Nicholas A. Fiore, P.E

**Engineering Ventures** nikf@engineeringventures.com 802.863.6225

STRUCTURAL ENGINEER

Bob Neeld, P.E, President Engineering Ventures bobn@engineeringventures.com 802.863.6225

MECH./PLUMBING ENGINEER

Daniel Dupras, P.E. Engineering Services of Vermont, LLC daniel.dupras@esvtllc.com 802.885.8091

ELECTRICAL ENGINEER

Claus Bartenstein, P.E., LEED-AP Engineering Services of Vermont, LLC claus.bartenstein@esvtllc.com 802.885.8091


CONSTRUCTION MANAGER Calvin Russell, Senior Project Manager ReArch Company, Inc. calvinr@rearchcompany.com 802.863.8727

DATE ISSUED: 03/31/2023 Drawn: JWF

Checked: NAF

REVISIONS:

# Date Description 04.12.2023 ADDENDUM #1; BID SET #1 2 05.15.2023 SCOPE CHANGES TO BID SET#1




PERMIT SET 05/15/2023

KUA KILTON/WELCH DORMITORIES

Main Street, Meriden, NH 03770

SITE PLAN





ASHAR NELSON, AIA, LEED AP ashar@vermontintegratedarchitecture.com

P.O. Box 862 Middlebury, VT 05753 802.989.7249

CIVIL ENGINEER
Nicholas A. Fiore, P.E
Engineering Ventures
nikf@engineeringventures.com

802.863.6225

STRUCTURAL ENGINEER
Bob Neeld, P.E, President

Engineering Ventures bobn@engineeringventures.com 802.863.6225

MECH./PLUMBING ENGINEER
Daniel Dupras, P.E.
Engineering Services of Vermont, LLC

daniel.dupras@esvtllc.com 802.885.8091

ELECTRICAL ENGINEER

Claus Bartenstein, P.E., LEED-AP
Engineering Services of Vermont, LLC
claus.bartenstein@esvtllc.com
802.885.8091

CONSTRUCTION MANAGER
Calvin Russell, Senior Project Manager
ReArch Company, Inc.
calvinr@rearchcompany.com
802.863.8727

DATE ISSUED: 03/31/2023 Drawn: JWF

Checked: NAF REVISIONS:

# Date Description
1 04.12.2023 ADDENDUM #1; BID SET #1
2 05.15.2023 SCOPE CHANGES TO

BID SET#1




PERMIT SET 05/15/2023


KUA KILTON/WELCH DORMITORIES

Main Street, Meriden, NH 03770

GRADING AND DRAINAGE PLAN

C2.2





### VERMONT INTEGRATED

ANDREA MURRAY, AIA, NCARB, LEED AP andrea@vermontintegratedarchitecture.com

ARCHITECTURE, PC

ASHAR NELSON, AIA, LEED AP ashar@vermontintegratedarchitecture.com

P.O. Box 862 Middlebury, VT 05753 802.989.7249

2.989./249

CIVIL ENGINEER

Nicholas A. Fiore, P.E Engineering Ventures nikf@engineeringventures.com 802.863.6225

STRUCTURAL ENGINEER

Bob Neeld, P.E, President Engineering Ventures bobn@engineeringventures.com 802.863.6225

MECH./PLUMBING ENGINEER

Daniel Dupras, P.E. Engineering Services of Vermont, LLC daniel.dupras@esvtllc.com 802.885.8091

ELECTRICAL ENGINEER

Claus Bartenstein, P.E., LEED-AP Engineering Services of Vermont, LLC claus.bartenstein@esvtllc.com 802.885.8091

CONSTRUCTION MANAGER
Calvin Russell, Senior Project Manager
ReArch Company, Inc.
calvinr@rearchcompany.com
802.863.8727


DATE ISSUED: 03/31/2023 Drawn: JWF

REVISIONS:

Checked: NAF

# Date Description

1 04.12.2023 ADDENDUM #1; BID SET #1
2 05.15.2023 SCOPE CHANGES TO
BID SET#1




PERMIT SET 05/15/2023

#### KUA KILTON/WELCH DORMITORIES

Main Street, Meriden, NH 03770

UTILITY PLAN

C2.3



# VERMONT INTEGRATED ARCHITECTURE, PC

ANDREA MURRAY, AIA, NCARB, LEED AP andrea@vermontintegratedarchitecture.com

ASHAR NELSON, AIA, LEED AP ashar@vermontintegratedarchitecture.com

P.O. Box 862 Middlebury, VT 05753 802.989.7249

CIVIL ENGINEER

Nicholas A. Fiore, P.E
Engineering Ventures
nikf@engineeringventures.com

802.863.6225

STRUCTURAL ENGINEER

Bob Neeld, P.E, President Engineering Ventures bobn@engineeringventures.com 802.863.6225

MECH./PLUMBING ENGINEER

Daniel Dupras, P.E. Engineering Services of Vermont, LLC daniel.dupras@esvtllc.com 802.885.8091

ELECTRICAL ENGINEER

Claus Bartenstein, P.E., LEED-AP
Engineering Services of Vermont, LLC

claus.bartenstein@esvtllc.com

802.885.8091

802.863.8727

CONSTRUCTION MANAGER
Calvin Russell, Senior Project Manager

ReArch Company, Inc. calvinr@rearchcompany.com


DATE ISSUED: 03/27/2023 Drawn: JWF

revisions:

Checked: NAF

# Date Description
1 04.12.2023 ADDENDUM #1; BID SET #1
2 05.15.2023 SCOPE CHANGES TO

BID SET#1




PERMIT SET 05/15/2023


KUA
KILTON/WELCH
DORMITORIES

Main Street, Meriden, NH 03770


EROSION CONTROL PLAN

C2.4







SEWER PROFILE "B", STA. 0+00 - 0+89





SEWER PROFILE "C", STA. 0+00 - 0+41SCALE: HORIZ. 1" = 20' VERT.: 1" = 10'



SEWER PROFILE "A", STA. 0+00 - 3+40SCALE: HORIZ. 1" = 20' VERT.: 1" = 10'









ANDREA MURRAY, AIA, NCARB, LEED AP andrea@vermontintegratedarchitecture.com

ASHAR NELSON, AIA, LEED AP ashar@vermontintegratedarchitecture.com

P.O. Box 862 Middlebury, VT 05753 802.989.7249

**CIVIL ENGINEER** Nicholas A. Fiore, P.E **Engineering Ventures** nikf@engineeringventures.com 802.863.6225

STRUCTURAL ENGINEER

Bob Neeld, P.E, President Engineering Ventures bobn@engineeringventures.com 802.863.6225

MECH./PLUMBING ENGINEER

Daniel Dupras, P.E. Engineering Services of Vermont, LLC daniel.dupras@esvtllc.com 802.885.8091

ELECTRICAL ENGINEER Claus Bartenstein, P.E., LEED-AP Engineering Services of Vermont, LLC

claus.bartenstein@esvtllc.com

802.885.8091


802.863.8727

CONSTRUCTION MANAGER Calvin Russell, Senior Project Manager ReArch Company, Inc. calvinr@rearchcompany.com

DATE ISSUED: 04/25/2023 Drawn: JWF

Checked: NAF **REVISIONS:** 

# Date Description 1 05.15.2023 SCOPE CHANGES TO BID SET#1




PERMIT SET 05/15/2023


KUA KILTON/WELCH **DORMITORIES** 


Main Street, Meriden, NH 03770

SEWER PLAN AND PROFILES 1

C3.1







VERMONT INTEGRATED ARCHITECTURE, PC

ANDREA MURRAY, AIA, NCARB, LEED AP andrea@vermontintegratedarchitecture.com

ASHAR NELSON, AIA, LEED AP ashar@vermontintegratedarchitecture.com

P.O. Box 862 Middlebury, VT 05753 802.989.7249

CIVIL ENGINEER
Nicholas A. Fiore, P.E
Engineering Ventures
nikf@engineeringventures.com
802.863.6225

STRUCTURAL ENGINEER

Bob Neeld, P.E, President
Engineering Ventures
bobn@engineeringventures.com

802.863.6225

MECH./PLUMBING ENGINEER

Daniel Dupras, P.E.
Engineering Services of Vermont, LLC
daniel.dupras@esvtllc.com
802.885.8091

ELECTRICAL ENGINEER
Claus Bartenstein, P.E., LEED-AP
Engineering Services of Vermont, LLC

claus.bartenstein@esvtllc.com

802.885.8091

802.863.8727

CONSTRUCTION MANAGER

Calvin Russell, Senior Project Manager

ReArch Company, Inc.

calvinr@rearchcompany.com


DATE ISSUED: 04/25/2023 Drawn: JWF

Checked: NAF

REVISIONS:

# Date Description

1 05.15.2023 SCOPE CHANGES TO BID SET#1




PERMIT SET 05/15/2023

KUA
KILTON/WELCH
DORMITORIES

Main Street, Meriden, NH 03770

SEWER PLAN AND PROFILES 2

C3.2



VERMONT INTEGRATED
ARCHITECTURE, PC

ANDREA MURRAY, AIA, NCARB, LEED AP andrea@vermontintegratedarchitecture.com

ASHAR NELSON, AIA, LEED AP ashar@vermontintegratedarchitecture.com

P.O. Box 862 Middlebury, VT 05753 802.989.7249

CIVIL ENGINEER

Nicholas A. Fiore, P.E

Engineering Ventures

nikf@engineeringventures.com

802.863.6225

STRUCTURAL ENGINEER

Bob Neeld, P.E, President
Engineering Ventures
bobn@engineeringventures.com
802.863.6225

MECH./PLUMBING ENGINEER

Daniel Dupras, P.E.
Engineering Services of Vermont, LLC
daniel.dupras@esvtllc.com
802.885.8091

ELECTRICAL ENGINEER

Claus Bartenstein, P.E., LEED-AP
Engineering Services of Vermont, LLC
claus.bartenstein@esvtllc.com
802.885.8091

CONSTRUCTION MANAGER
Calvin Russell, Senior Project Manager
ReArch Company, Inc.
calvinr@rearchcompany.com
802.863.8727

DATE ISSUED: 03/27/2023 Drawn: EV

Checked: NAF REVISIONS:

# Date Description

1 05.15.2023 SCOPE CHANGES TO
BID SET#1




PERMIT SET 05/15/2023

KUA
KILTON/WELCH
DORMITORIES


Main Street, Meriden, NH 03770

SITE DETAILS

C4.1



- 3. FOR SEWER LINES THE MINIMUM DEPTH TO THE TOP OF THE PIPE SHALL BE 6'-0" IN PAVED AREAS AND 4'-0" IN UNPAVED AREAS. SHALLOWER DEPTHS REQUIRE APPROVAL FROM THE ENGINEER. REFER TO INSULATION OVER SHALLOW
- SEWER LINE DETAIL. 4. LEDGE, ROCK, BOULDERS AND LARGE STONES SHALL BE REMOVED TO PROVIDE A MINIMUM CLEARANCE OF SIX INCHES BELOW AND ON EACH SIDE OF ALL PIPES.
- 5. TRENCH BACKFILL MATERIAL, INCLUDING ROADWAY LOCATIONS, SHALL BE NATURAL MATERIALS EXCAVATED FROM THE TRENCH DURING CONSTRUCTION AND FREE OF UNSUITABLE MATERIALS AS DEFINED IN THE EARTHWORK SPECIFICATIONS
- 6. WHEN APPLICABLE INSTALL PIPE WITH BELL ENDS DOWN SLOPE. PREVENT SEDIMENT FROM ENTERING NEW SEWER SYSTEM DURING CONSTRUCTION.
- 7. ALLOWABLE TRENCH WIDTH AT A PLANE 12 INCHES ABOVE THE PIPE SHALL BE NO MORE THAN 36 INCHES FOR SEWER PIPE LESS THAN 15 INCHES IN DIAMETER.
- 8. NO MECHANICAL TAMPERS SHALL BE USED DIRECTLY OVER PIPE TO INSURE PIPE IS NOT DAMAGED. 9. BACKFILL MATERIALS SHALL BE COMPACTED. IN 12" LAYERS. TO 92% OF MODIFIED PROCTOR (ASTM 1557) TO WITHIN 3 FEET OF FINISHED GRADE. IN AREAS UNDER ROADWAYS, DRIVES, AND PARKING THE UPPER 3 FEET SHALL BE COMPACTED, IN 6" LAYERS, TO 95% MODIFIED PROCTOR (ASTM 1557) AND IN LAWN OR OTHER UNDEVELOPED SPACE THE UPPER 3



NOTES:


1. REFER TO APPLICABLE TRENCH DETAIL FOR SPECIFIC BACKFILL INFORMATION. NOTIFY DEPARTMENT OF PUBLIC WORKS TO REVIEW INSTALLATION AND BACKFILL.

FEET SHALL BE COMPACTED TO 92% MODIFIED PROCTOR.

ALL SHALLOW SEWER INSTALLATIONS MUST BE APPROVED BY ENGINEER. 4. THE MINIMUM DEPTH TO THE TOP OF THE PIPE SHALL BE 6'-0" IN PAVED AREAS AND 4'-0" IN UNPAVED AREAS. SHALLOWER DEPTHS REQUIRE APPROVAL FROM THE ENGINEER. REFER TO INSULATION OVER SHALLOW SEWER LINE DETAIL.




TABLE FOR WIDTH AND THICKNESS



REFER TO STRUCTURAL DETAILS FOR REINFORCING AT WALL OPENINGS. REFER TO MECHANICAL AND ELECTRICAL PLANS FOR OPENING LOCATIONS

EXTERIOR BELOW GRADE WALL PENETRATION





INVERTS OF MANHOLES SHALL BE FORMED WITH GRADE SS - HARD BRICK CONFORMING TO ASTM C32-13.

- PROVIDE SMOOTH SWEEPING TRANSITIONS BETWEEN INVERTS OF INTERSECTING PIPE. 3. IF DEPTH OF MANHOLE IS 6 FT. OR LESS FROM RIM TO CENTERLINE INVERT, THEN A FLAT TOP MAY BE INSTALLED. IF DEPTH OF MANHOLE FROM RIM TO CENTERLINE INVERT IS MORE THAN 6 FT., THEN AN ECCENTRIC CONICAL TOP SHALL BE INSTALLED.
- MANHOLES SHALL HAVE A BRICK PAVED SHELF AND INVERT CONSTRUCTED TO CONFORM TO THE SIZE OF PIPE AND FLOW. AT CHANGES IN DIRECTION, THE INVERTS SHALL BE LAID OUT IN CURVES OF THE LONGEST RADIUS POSSIBLE TANGENT TO THE CENTER LINE OF THE SEWER PIPES. SHELVES SHALL BE CONSTRUCTED TO THE ELEVATION OF THE HIGHEST PIPE CROWN AND SLOPED TO DRAIN TOWARD THE FLOWING THROUGH CHANNEL. UNDERLAYMENT OF THE INVERT AND SHELF SHALL CONSIST OF BRICK MASONRY. INVERTS AND SHELVES SHALL BE PLACED AFTER TESTING.
- MANHOLE AND COVER SHALL BE DESIGNED FOR H20 LOADING. MANHOLE SHALL CONFORM TO ASTM C478 SPECIFICATIONS FOR "PRECAST REINFORCED CONCRETE MANHOLE
- CONCRETE FC=4,000 PSI @ 28 DAYS MINIMUM

8. BASE SECTION SHALL BE A ONE POUR MONOLITHIC SECTION









ANDREA MURRAY, AIA, NCARB, LEED AP andrea@vermontintegratedarchitecture.com

ASHAR NELSON, AIA, LEED AP ashar@vermontintegratedarchitecture.com

P.O. Box 862 Middlebury, VT 05753 802.989.7249

CIVIL ENGINEER Nicholas A. Fiore, P.E **Engineering Ventures** nikf@engineeringventures.com 802.863.6225

STRUCTURAL ENGINEER Bob Neeld, P.E, President Engineering Ventures bobn@engineeringventures.com 802.863.6225

MECH./PLUMBING ENGINEER Daniel Dupras, P.E. Engineering Services of Vermont, LLC daniel.dupras@esvtllc.com 802.885.8091

ELECTRICAL ENGINEER Claus Bartenstein, P.E., LEED-AP Engineering Services of Vermont, LLC claus.bartenstein@esvtllc.com 802.885.8091

CONSTRUCTION MANAGER Calvin Russell, Senior Project Manager ReArch Company, Inc. calvinr@rearchcompany.com 802.863.8727

DATE ISSUED: 03/27/2023 Drawn: EV Checked: NAF

REVISIONS: # Date Description




PERMIT SET 05/15/2023

#### KUA KILTON/WELCH **DORMITORIES**

Main Street, Meriden, NH 03770

SEWER DETAILS



TO 92% MODIFIED PROCTÒR.

1. UNLESS OTHERWISE NOTED, ASSUME CLASS "C" SOILS. PERFORM ALL EXCAVATIONS TO OSHA REQUIREMENTS.

- 2. BEDDING TO PROVIDE A FIRM, STABLE, CONTINUOUS AND UNIFORM SUPPORT FOR FULL LENGTH OF PIPE. 3. PROVIDE 6'-0" MINIMUM COVER OVER WATER PIPE. OTHERWISE, REFER TO INSULATION OVER SHALLOW WATER LINE DETAIL. 4. INSTALL WATER PIPE IN ACCORDANCE WITH AWWA STANDARD C600.
- 5. LEDGE, ROCK, BOULDERS AND LARGE STONES SHALL BE REMOVED TO PROVIDE A MINIMUM CLEARANCE OF SIX INCHES BELOW AND ON EACH SIDE OF ALL PIPES.
- 6. TRENCH BACKFILL MATERIAL, INCLUDING ROADWAY LOCATIONS, SHALL BE NATURAL MATERIALS EXCAVATED FROM THE TRENCH DURING CONSTRUCTION AND FREE OF UNSUITABLE MATERIALS AS DEFINED IN THE EARTHWORK SPECIFICATIONS INCLUDED ON THESE
- 7. NO MECHANICAL TAMPERS SHALL BE USED DIRECTLY OVER PIPE TO INSURE PIPE IS NOT DAMAGED. 8. BACKFILL MATERIALS SHALL BE COMPACTED, IN 12" LAYERS, TO 92% OF MODIFIED PROCTOR (ASTM 1557) TO WITHIN 3 FEET OF FINISHED GRADE. IN AREAS UNDER ROADWAYS, DRIVES, AND PARKING THE UPPER 3 FEET SHALL BE COMPACTED, IN 6" LAYERS, TO 95% MODIFIED PROCTOR (ASTM 1557) AND IN LAWN OR OTHER UNDEVELOPED SPACE THE UPPER 3 FEET SHALL BE COMPACTED




TABLE 2 - THRUST DEVELOPED PER 100psi PRESSURE (lbs force)						
PIPE DIAMETER IN.	VALVES AND DEAD ENDS, TEES	90° BENDS	45° BENDS	22 <sup>1</sup> / <sub>2</sub> * BENDS	11 <sup>1</sup> / <sub>4</sub> * BENDS	SECTION A-A
4	1810	2560	1390	635	320	NOTES:
6	3740	5290	2860	1370	690	- 1. PERFORM HYDROSTATIC AND LEAKAGE TEST PRESSURE PER
8	6430	9100	4920	2320	1170	SPECIFICATIONS.
10	9680	13680	7410	3610	1820	2. PLACE 4 MIL POLYETHYLENE BETWEEN FITTINGS AND THRUST
12	13690	19350	10470	5080	2550	BLOCKS.
14	18380	25990	14100	6100	3080	3. CONCRETE SHALL BE CLASS B. 4. ON ALL THRUST BLOCKS, B SHALL
16	23780	33630	18280	7960	4020	BE THE GREATER DIMENSION, USE
						1.5:1 TO 2:1 FOR B:H.

TABLE 1 - BEARING STRENGTH OF	UNDISTURBED SOIL
SOIL TYPE	BEARING STRENGTH
PEAT, ETC.	0 lb/ft <sup>2</sup>
SOFT CLAY	500 lb/ft <sup>2</sup>
SAND	1000 lb/ft <sup>2</sup>
SAND AND GRAVEL	1500 lb/ft <sup>2</sup>
SAND AND GRAVEL WITH CLAY	2000 lb/ft <sup>2</sup>
SAND AND GRAVEL CEMENTED WITH CLAY	4000 lb/ft <sup>2</sup>
HARD PAN	5000 lb/ft <sup>2</sup>


DETERMINING MINIMUM BEARING FACE AREA: THE AREA (ft<sup>2</sup>) SHALL BE CALCULATED BY DETERMINING THE TOTAL THRUST GENERATED AT THE FITTING.


DIVIDE THE THRUST DEVELOPED (lbs force) (FROM TABLE 2) BY THE BEARING STRENGTH OF THE SOIL (FROM TABLE 1). THE RESULT IS THE AREA OF THE SOIL REQUIRED TO RESIST THE

THE AREA CALCULATED WILL BE FOR THE AREA OF CONCRETE UP AGAINST THE TRENCH WALL (i.e. THE BACK SIDE OF THE BLOCK). <u>USE THE TEST PRESSURE TO DETERMINE THE TOTAL THRUST.</u>

AREA = THRUST DEVELOPED (lbs force)
BEARING STRENGTH OF SOIL

TYPICAL BEARING THRUST BLOCK






NOTES:


1. AREA OF THRUST BLOCK BEARING AGAINST UNDISTURBED SOIL SHALL BE THE SAME AS FOR 1/4" BEND (90°) BEND. 2. UTILIZE MEGALUG MECHANICAL JOINT RESTRAINT ON M.J. END.

3. SEE TYPICAL GATE VALVE DETAIL FOR VALVE BOX INFORMATION. 4. SEE TYPICAL WATER TRENCH DETAIL FOR PIPE BEDDING REQUIREMENTS.



NOTES:

1. ALL MATERIALS AND INSTALLATION PROCEDURES WILL CONFORM TO TECHNICAL SPECIFICATIONS. 2. ALL PIPE SHOULD HAVE A MINIMUM DEPTH OF 5' FROM TOP OF PIPE TO FINISHED GRADE





ANDREA MURRAY, AIA, NCARB, LEED AP andrea@vermontintegratedarchitecture.com

ASHAR NELSON, AIA, LEED AP ashar@vermontintegratedarchitecture.com

P.O. Box 862 Middlebury, VT 05753 802.989.7249

CIVIL ENGINEER Nicholas A. Fiore, P.E Engineering Ventures nikf@engineeringventures.com 802.863.6225

STRUCTURAL ENGINEER Bob Neeld, P.E, President Engineering Ventures bobn@engineeringventures.com

802.863.6225

MECH./PLUMBING ENGINEER Daniel Dupras, P.E.

Engineering Services of Vermont, LLC daniel.dupras@esvtllc.com 802.885.8091

ELECTRICAL ENGINEER Claus Bartenstein, P.E., LEED-AP Engineering Services of Vermont, LLC claus.bartenstein@esvtllc.com 802.885.8091

CONSTRUCTION MANAGER Calvin Russell, Senior Project Manager ReArch Company, Inc. calvinr@rearchcompany.com 802.863.8727

DATE ISSUED: 03/27/2023 Drawn: EV Checked: NAF

**REVISIONS:** # Date Description




PERMIT SET 05/15/2023

#### KUA KILTON/WELCH DORMITORIES

Main Street, Meriden, NH 03770

WATER DETAILS





PIĆK HOLES


MANHOLE (MH) FRAME AND COVER ASSEMBLY SHALL BE EAST JORDAN IRON WORKS "1480A V1419 ASSEMBLY"


COVERS AND CB


SECTION VIEW MANHOLE
















ANDREA MURRAY, AIA, NCARB, LEED AP andrea@vermontintegratedarchitecture.com

ASHAR NELSON, AIA, LEED AP ashar@vermontintegratedarchitecture.com

P.O. Box 862 Middlebury, VT 05753 802.989.7249

CIVIL ENGINEER Nicholas A. Fiore, P.E **Engineering Ventures** nikf@engineeringventures.com 802.863.6225

STRUCTURAL ENGINEER Bob Neeld, P.E, President

Engineering Ventures bobn@engineeringventures.com 802.863.6225

MECH./PLUMBING ENGINEER Daniel Dupras, P.E. Engineering Services of Vermont, LLC daniel.dupras@esvtllc.com

802.885.8091

802.885.8091

ELECTRICAL ENGINEER Claus Bartenstein, P.E., LEED-AP Engineering Services of Vermont, LLC claus.bartenstein@esvtllc.com


CONSTRUCTION MANAGER Calvin Russell, Senior Project Manager ReArch Company, Inc. calvinr@rearchcompany.com 802.863.8727

DATE ISSUED: 03/27/2023 Drawn: EV

Checked: NAF

**REVISIONS:** 

# Date Description 1 04.12.2023 ADDENDUM #1; BID SET #1 2 05.15.2023 SCOPE CHANGES TO




PERMIT SET 05/15/2023

KUA KILTON/WELCH **DORMITORIES** 

Main Street, Meriden, NH 03770

STORMWATER **DETAILS** 




OR APPROVED EQUAL.


TOP VIEW

ALL DIMENSIONS SHOWN HERE ARE NOMINAL.

COVER SHALL BE HEAVY DUTY (H-20) LOAD RATED.



- 1. SILT FENCE SHALL BE PRE-FABRICATED EROSION CONTROL FENCE BY MIRAFI OR EQUAL, OR CONSTRUCTED IN PLACE AS SPECIFIED HEREIN.
- 2. CONSTRUCTED IN PLACE SILT FENCE: A. WOVEN WIRE FENCE TO BE FASTENED SECURELY TO FENCE POSTS WITH WIRE TIES OR STAPLES. B. FILTER FABRIC TO BE FASTENED SECURELY TO WOVEN WIRE FENCE TIES SPACED EVERY 24" AT TOP OF MID SECTION. C. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER, THEY SHALL BE OVERLAPPED BY 6", FOLDED AND
- 3. INSPECTION SHALL BE FREQUENT (MINIMUM ONCE A WEEK AND AFTER EVERY RAINFALL). MAINTENANCE SHALL BE PERFORMED AS NEEDED, AND SEDIMENT REMOVED WHEN "BULGES" DEVELOP IN SILT FENCE.






SLOPE SURFACE SHALL BE FREE OF ROCKS, CLODS, STICKS AND GRASS. MATS/BLANKETS SHALL HAVE GOOD SOIL CONTACT.


THERE SHALL BE NO PLASTIC. OR MULTI-FILAMENT OR MONOFILAMENT POLYPROPYLENE NETTING OR MESH WITH AN OPENING


LAY BLANKETS LOOSELY AND STAKE OR STAPLE TO MAINTAIN DIRECT CONTACT WITH THE SOIL. DO NOT STRETCH.



- SEEDING AND MULCHING OF DISTURBED AREAS SHALL TAKE PLACE WITHIN 48 HOURS OF FINAL GRADING. MULCH: HAY SHALL NOT BE USED. STRAW MULCH SHALL BE UTILIZED AND SHALL BE APPLIED AT A RATE OF 90-1,000 LBS/1,000 SF. MULCH SHALL NOT BE PLACED ON SLOPES OF GREATER THAN 3:1. SEED IMPREGNATED
- EROSION CONTROL NETTING SHALL BE USED IN ITS PLACE. SEED: SEEDING SHALL OCCUR AFTER APRIL 15 AND PRIOR TO SEPTEMBER 15TH IN ORDER TO ESTABLISH A STAND OF GRASS PRIOR TO GROUND FREEZING. SEED SHALL BE IN ACCORDANCE WITH SEED SPECIFICATION ON THIS SHEET.
- COVER SEED WITH  $\frac{1}{4}$  INCH SOIL UNLESS A HYDROSEEDER IS USED. MULCH ANCHORING: SHALL BE ACCOMPLISHED BY DEGRADABLE MULCH NETTING. USE WHEN SLOPES ARE GREATER
- TOPSOIL AND MULCHING NOT TO BE APPLIED IN AREAS OF TRAVEL WAYS.

APPLY PERMANENT SEEDING BEFORE PLACING BLANKETS.





STONE WILL BE PLACED ON A FILTER FABRIC FOUNDATION TO THE LINES, GRADES AND LOCATIONS SHOWN IN SET SPACING OF CHECK DAMS TO ASSUME THAT THE ELEVATIONS OF THE CREST OF THE DOWNSTREAM DAM IS

AT THE SAME ELEVATION OF THE TOE OF THE UPSTREAM DAM. EXTEND THE STONE A MINIMUM OF 1.5 FEET BEYOND THE DITCH BANKS TO PREVENT CUTTING AROUND THE DAM. PROTECT THE CHANNEL DOWNSTREAM OF THE LOWEST DAM FROM SCOUR AND EROSION WITH STONE OR LINER AS APPROPRIATE.

ENSURE THAT CHANNEL APPURTENANCES SUCH AS CULVERT ENTRANCES BELOW CHECK DAMS ARE NOT SUBJECT TO DAMAGE OR BLOCKAGE FROM DISPLACED STONES.

REMOVE ACCUMULATED SEDIMENT BEHIND CHECK DAM WHEN 1/2 THE HEIGHT OF THE DAM. REPLACE STONES AS NECESSARY.

MOUNTABLE BERM -**EXISTING PAVEMENT-**50' MINIMUM 2% MIN. EXISTING GROUND MIRAFI 500X FILTER FABRIC OR EQUAL. **PAVEMENT** PROFILE 50' MINIMUM 10'-0" **SAWCUT** EXISTING GROUND **EXISTING PAVEMENT** PLAN VIEW **EXISTING** PAVEMENT

1. STONE SIZE: USE 3" (MIN) CRUSHED STONE.

2. SURFACE WATER - ALL SÚRFACE WATER FLOWING OR DIVERTED TOWARD CONSTRUCTION ENTRANCE SHALL BE PIPED ACROSS THE ENTRANCE.

MAINTENANCE — THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHT-OF-WAYS. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND. REPAIR AND/OR CLEANOUT ANY MEASURES USED TO TRAP SEDIMENT. TRACKING ONTO PUBLIC RIGHT-OF-WAYS SHALL **NOT** BE ALLOWED. ALL SEDIMENT SPILLED, DROPPED, OR WASHED ONTO PUBLIC RIGHT-OF-WAYS MUST BE REMOVED IMMEDIATELY AND ANY WASH WATER MUST BE CONTAINED AND PROPERLY

DISPOSED OF. PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER EACH RAIN.

WHEELS SHALL BE CLEANED TO REMOVE MUD PRIOR TO ENTRANCE ONTO PUBLIC RIGHT-OF-WAY. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH STONE WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE.

STABILIZED CONSTRUCTION

## EROSION CONTROL NOTES

— TOP OF

APRON LENGTH (5' MIN.)

UNDISTURBED

GROUND

- CHANNEL SIDE

FORMED BY

COMPACTED

EMBANKMENT OR

EXCAVATED INTO

- WEIR CREST

STONE THICKNESS

-stone lined outlet as per table

FIT EXISTING TOPOGRAPHY)

PERSPECTIVE VIEW

THE MINIMUM VOLUME OF THE TRAP SHALL BE 3,600 CUBIC FEET OF STORAGE FOR EACH ACRE OF DRAINAGE AREA;

THE SIDE SLOPES OF THE TRAP SHALL BE 3:1 OR FLATTER, AND SHALL BE STABILIZED IMMEDIATELY AFTER THEIR

THE TRAP SHALL BE INSTALLED AS CLOSE TO THE DISTURBED AREA OR SOURCE OF SEDIMENT AS POSSIBLE;

THE OUTLET OF THE TRAP SHALL BE A MINIMUM OF ONE FOOT BELOW THE CREST OF THE TRAP AND SHALL

9. THE AREA UNDER EMBANKMENT SHALL BE CLEARED, GRUBBED AND STRIPPED OF ANY VEGETATION AND ROOT MAT.

10. The fill material for the embankment shall be free of roots or other woody vegetation as well as

12. FILTER CLOTH SHALL BE PLACED OVER THE BOTTOM AND SIDES OF THE OUTLET CHANNEL PRIOR TO PLACEMENT OF

STONE. SECTIONS OF FABRIC MUST OVERLAP AT LEAST ONE (1) FOOT WITH SECTION NEAREST THE ENTRANCE

13. STONE USED IN THE OUTLET CHANNEL SHALL BE FOUR (4) TO EIGHT (8) INCH RIPRAP. TO PROVIDE A FILTERING

16. THE STRUCTURE SHALL BE REMOVED AND THE AREA STABILIZED WHEN DRAINAGE AREA HAS BEEN PROPERLY

PLACED ON TOP. FABRIC SHALL BE EMBEDDED AT LEAST SIX (6) INCHES INTO EXISTING GROUND AT ENTRANCE

EFFECT, A LAYER OF FILTER CLOTH SHALL BE EMBEDDED ONE (1) FOOT WITH SECTION NEAREST ENTRANCE PLACED

ON TOP. FABRIC SHALL BE EMBEDDED AT LEAST SIX (6) INCHES INTO EXISTING GROUND AT ENTRANCE OF OUTLET

11. ELEVATION OF THE TOP OF ANY DIKE DIRECTING WATER INTO TRAP MUST EQUAL OR EXCEED THE HEIGHT OF

OVER-SIZED STONES, ROCKS, ORGANIC MATERIAL OR OTHER OBJECTIONABLE MATERIAL. THE EMBANKMENT SHALL BE

COMPACTED BY TRAVERSING WITH EQUIPMENT WHILE IT IS BEING CONSTRUCTED. MAXIMUM HEIGHT OF EMBANKMENT

AND THE MATERIALS REMOVED FROM THE TRAP SHALL BE PROPERLY DISPOSED OF AND STABILIZED.

THE MAXIMUM CONTRIBUTING DRAINAGE AREA TO THE TRAP SHALL BE LESS THAN 5 ACRES

THE TRAP SHALL BE CLEANED WHEN 50 PERCENT OF THE ORIGINAL VOLUME IS FILLED;

SHALL BE FIVE (5) FEET, MEASURED AT CENTERLINE OF EMBANKMENT.

14. THE STRUCTURE SHALL BE INSPECTED AFTER EACH RAIN AND REPAIRED AS NEEDED.

ST-VI (CHANNEL MAY BE CURVED TO

STONE SIZE TO BE 4" TO 8"

EMBANKMENT OR

EXISTING GROUND

- TOP OF COMPACTED EMBANKMENT I' ABOVE TOP OF STONE LINING MAX.

5' ABOVE EXISTING GROUND AT C

CLOTH -

├─LENGTH OF WEIR (b)-

MAX. DEPTH OF

FLOW (A)

**PROFILE** 

4' MIN. TOP WIDT

- MIN. 1% FALL

CROSS SECTION

— FILTER CLOTH (EMBEDDED MIN.

4" AT UPSTREAM END)

MAX. 3:1 SLOPE -

EXISTING GROUND -

WEIR CREST TO B

EXISTING GROUND AT

C OF EMBANKMENT

EXISTING GROUND

EXCAVATE FOR STORAGE

MINIMUM VOLUME OF

COMPACTED

FLARE APRON TO

EQUAL 1.5x WEIR

LENGTH (b) AT END

CONSTRUCTION:

OUTLET CHANNEL.

STABILIZED.

DISCHARGE TO A STABILIZED AREA;

THE POOL AREA SHALL BE CLEARED.

EMBANKMENT

TRAP = 3,600 CF

1/2 X A BELOW

. To adequately protect water quality during cold weather and during spring runoff, the additional stabilization techniques SPECIFIED IN THIS SECTION SHALL BE EMPLOYED DURING THE PERIOD FROM OCTOBER 15 THROUGH MAY

THE AREA OF EXPOSED. UNSTABILIZED SOIL SHALL BE LIMITED TO ONE ACRE AND SHALL BE PROTECTED AGAINST EROSION BY THE METHODS DESCRIBED IN THIS SECTION PRIOR TO ANY THAW OR SPRING MELT EVENT. THE ALLOWABLE AREA OF EXPOSED SOIL MAY BE INCREASED IF A WINTER CONSTRUCTION PLAN, DEVELOPED BY A QUALIFIED ENGINEER OR A CPESC SPECIALIST, IS REVIEWED AND APPROVED BY NHDES.

ALL PROPOSED VEGETATED AREAS WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OCTOBER 15TH. OR WHICH ARE DISTURBED AFTER OCTOBER 15TH, SHALL BE STABILIZED BY SEEDING AND INSTALLING EROSION CONTROL BLANKETS ON SLOPES GREATER THAN 3:1, AND SEEDING AND PLACING 3 TO 4 TONS OF MULCH PER ACRE, SECURED WITH ANCHORED NETTING, ELSEWHERE. THE INSTALLATION OF EROSION CONTROL BLANKETS OR MULCH AND NETTING SHALL NOT OCCUR OVER ACCUMULATED SNOW OR ON FROZEN GROUND AND SHALL BE COMPLETED IN ADVANCE OF THAW OR SPRING MELT EVENTS.

4. ALL DITCHES OR SWALES WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OCTOBER 15TH, OR WHICH ARE DISTURBED AFTER OCTOBER 15TH, SHALL BE STABILIZED TEMPORARILY WITH STONE OR EROSION CONTROL BLANKETS APPROPRIATE FOR THE DESIGN FLOW

AFTER OCTOBER 15TH, INCOMPLETE ROAD OR PARKING SURFACES, WHERE WORK HAS STOPPED FOR THE WINTER SEASON, SHALL BE PROTECTED WITH A MINIMUM OF 3 INCHES OF CRUSHED GRAVEL PER NHDOT ITEM 304.3.

ALL PROPOSED STABILIZATION IN ACCORDANCE WITH THE ABOVE SHALL BE COMPLETED WITHIN A DAY OF ESTABLISHING THE GRADE THAT IS FINAL OR THAT OTHERWISE WILL EXIST FOR MORE THAN 5 DAYS.

#### <u>General erosion control notes</u>

1. THE "ON-SITE EROSION CONTROL PLAN COORDINATOR" SHALL BE THE GENERAL CONTRACTOR, THIS INDIVIDUAL SHALL BE PRESENT ON-SITE FROM DAY-TO-DAY, AND SHALL BE RESPONSIBLE FOR ENSURING THAT THE EROSION CONTROL MEASURES REQUIRED BY THE EROSION CONTROL PLAN, DETAILS AND NOTES, ARE PROPERLY INSTALLED AND MAINTAINED. THE ONSITE EROSION CONTROL PLAN COORDINATOR SHALL KEEP A WRITTEN RECORD OF INSPECTIONS AND MAINTENANCE OF EROSION CONTROL FEATURES. A COPY OF THESE PLANS AND

INSPECTION/MAINTENANCE RECORDS SHALL BE KEPT ONSITE AT ALL TIMES. 2. THE SMALLEST PRACTICAL AREA OF LAND SHALL BE DISTURBED AT ANY ONE TIME DURING DEVELOPMENT. WHEN LAND IS DISTURBED, THE

DISTURBANCE SHALL BE KEPT TO THE SHORTEST PRACTICAL DURATION AS APPROVED BY THE OWNER'S REP. DUST SHALL BE CONTROLLED WITH WATER DISTRIBUTED BY A TRUCK MOUNTED SPRAY BAR. CALCIUM CHLORIDE(AASHTO M 144) OR SODIUM

CHLORIDE(AASHTO M 143) SHALL BE USED AS DIRECTED BY THE OWNER'S REP. 4. ALL EROSION AND STORMWATER CONTROL SYSTEMS SHALL BE INSPECTED ONCE EVERY 7 CALENDAR DAYS AND WITHIN 24 HOURS OF THE

OCCURRENCE OF A STORM EVENT OF 0.5" OR GREATER. NEEDED REPAIRS SHALL BE MADE IMMEDIATELY. SEDIMENT DEPOSITS SHALL BE REMOVED AS THEY ACCUMULATE AND PLACED IN AREAS WHERE FURTHER EROSION IS UNLIKELY EXISTING GROUND 5. A WRITTEN REPORT, STAMPED BY A QUALIFIED ENGINEER OR A CPESC SPECIALIST, SHALL BE SUBMITTED TO THE NHDES WITHIN 24 HOURS OF

A) DESCRIBES THE PROGRESS OF THE PROJECT, INCLUDING WHETHER ALL CONDITIONS OF THE PERMIT ARE BEING MET AND, IF NOT, WHICH

REQUIREMENTS ARE NOT BEING MET; B) IF ANY REQUIREMENTS ARE NOT BEING MET, AN EXPLANATION OF THE CORRECTIVE ACTION(S) THAT WILL BE OR ARE BEING TAKEN TO BRING THE PROJECT INTO COMPLIANCE WITH APPLICABLE REQUIREMENTS AND THE DEADLINE BY WHICH SUCH ACTIONS WILL BE COMPLETED; AND

C) INCLUDES PHOTOGRAPHS OF THE SITE THAT ARE REPRESENTATIVE OF THE PROJECT; AND 6. RETAIN A COPY OF THE REPORT PREPARED PURSUANT TO (5), ABOVE, ON-SITE FOR REVIEW DURING SITE INSPECTIONS BY FEDERAL, STATE, AND LOCAL OFFICIALS

ALL PERIMETER CONTROLS SHALL BE INSTALLED PRIOR TO EARTH MOVING OPERATIONS

DETENTION BASINS AND SWALES SHALL BE INSTALLED PRIOR TO ROUGH GRADING THE SITE ALL DITCHES AND SWALES SHALL BE STABILIZED PRIOR TO DIRECTING RUNOFF TO THEM.

10. ALL ROADWAYS AND PARKING LOTS SHALL BE STABILIZED WITHIN 72 HOURS OF ACHIEVING FINISHED GRADE.

11. ALL CUT AND FILL SLOPES SHALL BE SEEDED/LOAMED WITHIN 72 HOURS OF ACHIEVING FINISHED GRADE. 12. AN AREA SHALL BE CONSIDERED STABLE IF ONE OF THE FOLLOWING HAS OCCURRED:

- BASE COURSE GRAVELS HAVE BEEN INSTALLED IN AREAS TO BE PAVED:

 – A MINIMUM OF 85% VEGETATED GROWTH HAS BEEN ESTABLISHED; - A MINIMUM OF 3" OF NON-EROSIVE MATERIAL SUCH AS STONE OR RIPRAP HAS BEEN INSTALLED; OR

- EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED. 13. LOT DISTURBANCE OTHER THAN THAT SHOWN ON THE APPROVED PLANS SHALL NOT COMMENCE UNTIL AFTER THE ROADWAY HAS THE BASE

COURSE TO DESIGN ELEVATION AND THE ASSOCIATED DRAINAGE IS COMPLETE AND STABLE. 14. APPROPRIATE SILTATION/EROSION/TURBIDITY CONTROLS SHALL BE IN PLACE PRIOR TO CONSTRUCTION, SHALL BE MAINTAINED DURING

CONSTRUCTION, AND REMAIN IN PLACE UNTIL THE AREA IS STABILIZED. SILT FENCE(S) MUST BE REMOVED ONCE THE AREA IS STABILIZED

15. DISCHARGE FROM DEWATERING OF WORK AREAS SHALL BE TO SEDIMENT BASINS THAT ARE A) LOCATED IN UPLANDS;

B) LINED WITH HAY BALES OR OTHER ACCEPTABLE SEDIMENT TRAPPING LINERS; C) SET BACK AS FAR AS POSSIBLE FROM WETLANDS AND SURFACE WATERS, IN ALL CASES WITH A MINIMUM OF 20 FEET OF UNDISTURBED

WITHIN THREE DAYS OF FINAL GRADING, ALL EXPOSED SOIL AREAS SHALL BE STABILIZED BY SEEDING AND MULCHING DURING THE GROWING

SEASON, OR IF NOT WITHIN THE GROWING SEASON, BY MULCHING WITH TACK OR NETTING AND PINNING ON SLOPES STEEPER THAN 3:1.

17. WHERE CONSTRUCTION ACTIVITIES HAVE BEEN TEMPORARILY SUSPENDED WITHIN THE GROWING SEASON, ALL EXPOSED SOIL AREAS SHALL BE STABILIZED WITHIN 14 DAYS BY SEEDING AND MULCHING 18. WHERE CONSTRUCTION ACTIVITIES HAVE BEEN TEMPORARILY SUSPENDED OUTSIDE THE GROWING SEASON, ALL EXPOSED AREAS SHALL B

STABILIZED WITHIN 14 DAYS BY MULCHING AND TACK. SLOPES STEEPER THAN 3:1 SHALL BE STABILIZED BY MATTING AND PINNING. PROPER HEADWALLS SHALL BE CONSTRUCTED WITHIN SEVEN DAYS OF CULVERT INSTALLATION. 20. CULVERT OUTLETS SHALL BE PROTECTED IN ACCORDANCE WITH THE DES BEST MANAGEMENT PRACTICES FOR URBAN STORMWATER RUNOF

MANUAL (JANUARY 1996) AND THE STORMWATER MANAGEMENT AND EROSION AND SEDIMENT CONTROL HANDBOOK FOR URBAN AND DEVELOPING AREAS IN NEW HAMPSHIRE (AUGUST 1992).

21. THE CONTRACTOR RESPONSIBLE FOR COMPLETION OF THE WORK SHALL UTILIZE TECHNIQUES DESCRIBED IN THE NEW HAMPSHIRE STORMWATER MANUAL, VOLUME 3, EROSION AND SEDIMENT CONTROLS DURING CONSTRUCTION (DECEMBER 2008).

22. DO NOT PLACE THE BIORETENTION SYSTEM INTO SERVICE UNTIL ALL BMPS HAVE BEEN PLANTED AND ITS CONTRIBUTING AREAS HAVE BEEN FULLY 23. DO NOT DISCHARGE SEDIMENT-LADEN WATERS FROM THE CONSTRUCTION ACTIVITIES (RUNOFF, WATER FROM EXCAVATIONS) TO BIORETENTION AREA 15. CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN SUCH A MANNER THAT EROSION AND WATER POLLUTION ARE

DURING ANY STAGE OF CONSTRUCTION. 24. DO NOT TRAFFIC EXPOSED SOIL SURFACE WITH CONSTRUCTION EQUIPMENT. IF FEASIBLE, PERFORM EXCAVATIONS WITH EQUIPMENT POSITIONED

OUTSIDE THE LIMITS OF THE INFILTRATION COMPONENTS OF THE SYSTEM.

#### **EROSION CONTROL CONSTRUCTION SEQUENCE:**

1. THE "ON-SITE EROSION CONTROL PLAN COORDINATOR" SHALL BE THE GENERAL CONTRACTOR, THIS INDIVIDUAL SHALL BE PRESENT ON SITE FROM DAY TO DAY, AND SHALL BE RESPONSIBLE FOR ENSURING THAT THE EROSION CONTROL MEASURES REQUIRED BY THE EROSION CONTROL PLAN. DETAILS AND NOTES. ARE PROPERLY INSTALLED AND MAINTAINED. THE ONSITE EROSION CONTROL PLAN COORDINATOR SHALL KEEP A WRITTEN RECORD OF INSPECTIONS AND MAINTENANCE OF EROSION CONTROL FEATURES. A COPY OF THESE PLANS AND INSPECTION/MAINTENANCE RECORDS SHALL BE KEPT ONSITE AT ALL TIMES.

2. HOLD PRE-CONSTRUCTION CONFERENCE AT LEAST ONE WEEK PRIOR TO STARTING CONSTRUCTION, WITH THE CONTRACTOR, OWNER, AND ENGINEER. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ESTABLISHING ALL EROSION CONTROL MEASURES DELINEATED ON THE PLANS AND ANY ADDITIONAL MEASURES THAT ARE NECESSARY TO MINIMIZE EROSION. THE CONTRACTOR SHALL HAVE EROSION CONTROL MATERIALS AND INSTALLATION EQUIPMENT ON SITE AT ALL TIMES.

3. IF POSSIBLE, ALL TEMPORARY EROSION CONTROL MEASURES REQUIRED FOR WORK PROPOSED DURING THE WINTER (BETWEEN OCTOBER 15 AND MAY 1), SHALL BE INSTALLED PRIOR TO OCTOBER 1.

4. PRIOR TO ANY OTHER WORK, SILT FENCES SHALL BE INSTALLED GENERALLY 10 FEET FROM THE BASE OF THE FILL SLOPES, OR AS SHOWN ON THE EROSION CONTROL PLAN. THESE SHALL REMAIN IN PLACE AND BE MAINTAINED UNTIL THE PROJECT SITE HAS BEEN STABILIZED. SEDIMENT SHALL BE REMOVED FROM BEHIND THE SILT FENCE WHEN IT BECOMES 6 INCHES DEEP AT THE FENCE. THE SILT FENCE WILL BE REPAIRED AS NECESSARY TO MAINTAIN A PROPER SEDIMENT BARRIER.

INSTALL TEMPORARY GRAVEL CONSTRUCTION ENTRANCE/EXIT. INSTALL INLET PROTECTION ON EXISTING AND NEW CATCH BASINS.

ROUGH GRADE AND STOCKPILE TOPSOIL SURROUNDED BY SILT FENCE.

STABILIZE EXPOSED SLOPES AND SOILS AS SOON AS GRADED, AND MAINTAIN UNTIL ADEQUATELY VEGETATED

COMPLETE FINAL GRADING OF SITE. PLACE TOPSOIL AND PERMANENTLY VEGETATE, LANDSCAPE, AND MULCH. 10. AFTER THE SITE IS APPROVED BY THE ENGINEER AS ADEQUATELY STABILIZED, REMOVE ALL TEMPORARY MEASURES AND INSTALL PERMANENT

VEGETATION ON THE DISTURBED AREAS.

#### TEMPORARY/CONSTRUCTION EROSION CONTROL MEASURES:

HAY SHALL NOT BE USED. . SILT FENCES SHALL BE INSTALLED GENERALLY 10 FEET FROM THE BASE OF THE FILL SLOPES, OR AS SHOWN ON THE PLANS. THESE SHALL REMAIN IN PLACE UNTIL THE PROJECT SITE HAS BEEN STABILIZED. SEDIMENT SHALL BE REMOVED FROM BEHIND THE SILT FENCE WHEN IT BECOMES 6 INCHES DEEP AT THE FENCE. THE SILT FENCE WILL BE REPAIRED AS NECESSARY TO MAINTAIN A PROPER SEDIMENT BARRIER.

3. INSTALL STONE CHECK DAMS IN GRASS-LINED SWALES 50 FEET ON CENTER TO PREVENT SILT FROM WASHING INTO THE DRAINAGE SYSTEM DURING CONSTRUCTION. SEDIMENT SHALL BE REMOVED FROM BEHIND THE DAMS WHEN IT BECOMES 6 INCHES DEEP. STONE CHECK DAMS SHALL BE REMOVED WHEN VEGETATION IS ESTABLISHED.

4. DROP INLET PROTECTION SHALL BE PROVIDED AROUND ALL EXISTING AND PROPOSED CATCH BASINS. PROTECTION SHALL REMAIN UNTIL ALL DISTURBED AREAS ARE STABILIZED. SEDIMENT SHALL BE REMOVED FROM DROP INLET PROTECTION WHEN THE STORAGE CAPACITY HAS BEEN APPROXIMATELY 50% FILLED. GRAVEL WILL BE CLEANED OR REPLACED WHEN IT NO LONGER DRAINS PROPERLY. 5. EXCAVATED MATERIAL FROM EARTH EXCAVATION AND DITCH DIGGING SHALL BE DISPOSED OF OFFSITE OR USED FOR PROJECT FILL MATERIAL IF

DETERMINED SUITABLE BY THE OWNER'S REPRESENTATIVE. 6. STOCKPILED MATERIAL (TOPSOIL, BORROW, ETC.) SHALL HAVE SILT FENCE CONSTRUCTED AROUND THE PERIMETER. THE STOCKPILED MATERIAL SHALL BE SEEDED AND MULCHED AS SOON AS POSSIBLE TO PREVENT SOIL EROSION AND SEDIMENTATION OFF SITE. LOCATE STOCKPILES ON THE UPHILL SIDE OF DISTURBED AREAS, IF POSSIBLE. DURING WINDY CONDITIONS, STOCKPILED MATERIAL SHALL BE COVERED OR WATERED

#### PERMANENT EROSION CONTROL MEASURES:

APPROPRIATELY TO PREVENT WIND EROSION.

GRASS LINED SWALES SHALL BE TOP SOILED. SODDED AND FERTILIZED AREAS WHICH EXHIBIT SIGNS OF EROSION SHALL BE RE-SODDED IMMEDIATELY AND MAINTAINED UNTIL SOD HAS PERMANENT HOLD AND IS HEALTHY.

WHEN CONSTRUCTION IS COMPLETED IN AN AREA, IT SHALL BE IMMEDIATELY TOP SOILED, SEEDED, FERTILIZED AND MULCHED.

3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE CONTINUED MAINTENANCE OF ALL DISTURBED AREAS, INCLUDING WATERING, UNTIL THE AREA

IS INSPECTED AND ACCEPTED BY THE OWNER OR ENGINEER.

4. AFTER THE SITE IS STABILIZED, REMOVE ALL TEMPORARY MEASURES AND INSTALL PERMANENT VEGETATION ON THE DISTURBED AREAS. 5. RE-SEEDING SHALL BE DONE UNTIL ALL AREAS ARE COMPLETELY COVERED WITH A MATURE STRAND OF GRASS. AN AREA SHALL BE CONSIDERED COVERED WHEN THE ENTIRE SURFACE CONTAINS A VERDUROUS STAND OF GRASS. AREAS THAT, IN THE OPINION OF THE ENGINEER, ARE PREDOMINATELY WEEDS SHALL BE PLOWED UP, FINE GRADED, FERTILIZED AND RE-SEEDED IN THE MANNER SPECIFIED PREVIOUSLY, EXERCISING CAUTION NOT TO CAUSE DAMAGE TO NEW OR EXISTING PLANT MATERIAL.

vermont integrated

ANDREA MURRAY, AIA, NCARB, LEED AP andrea@vermontintegratedarchitecture.com

ASHAR NELSON, AIA, LEED AP ashar@vermontintegratedarchitecture.com

P.O. Box 862 Middlebury, VT 05753 802.989.7249

CIVIL ENGINEER

Nicholas A. Fiore, P.E Engineering Ventures nikf@engineeringventures.com 802.863.6225

STRUCTURAL ENGINEER Bob Neeld, P.E, President

Engineering Ventures bobn@engineeringventures.com 802.863.6225

MECH./PLUMBING ENGINEER

Daniel Dupras, P.E. Engineering Services of Vermont, LLC daniel.dupras@esvtllc.com 802.885.8091

ELECTRICAL ENGINEER Claus Bartenstein, P.E., LEED-AP Engineering Services of Vermont, LLC

claus.bartenstein@esvtllc.com


802.885.8091

CONSTRUCTION MANAGER Calvin Russell, Senior Project Manager ReArch Company, Inc. calvinr@rearchcompany.com 802.863.8727

DATE ISSUED: 03/27/2023 Drawn: EV

Checked: NAF **REVISIONS:** 

# Date Description 05.15.2023 SCOPE CHANGES TO BID SET#1





PERMIT SET 05/15/2023

KUA KILTON/WELCH **DORMITORIES** 

Meriden, NH 03770

**EROSION CONTROL** DETAILS





#### FIRE ALARM SYSTEM RISER DIAGRAM

#### FIRE RISER GENERAL NOTES:

- 1. COORDINATE FIRE ALARM SYSTEM DESIGN AND INSTALLATION WITH THE MUNICIPAL FIRE DEPARTMENT; SUBMIT SUBMITTAL DOCUMENTATION FOR THEIR REVIEW PRIOR TO ANY
- 2. FIRE ALARM SYSTEM SHALL MEET ALL VERMONT STATE CODE REQUIREMENTS. DEVICE INSTALLATION HEIGHTS AND SIGNAL COVERAGE SHALL MEET THE REQUIREMENTS OF THE AMERICANS WITH DISABILITIES ACT (ADA).
- 3. LOCATE FIRE ALARM EQUIPMENT AND DEVICES, GENERALLY, AS FOLLOWS:
- 3.1. MANUAL PULLSTATIONS: 3.2. VISUAL SIGNALS (STROBES): 84" AFF
- 3.3. REMOTE TEST STATIONS: 54" AFF
- 72" AFF TO TOP 3.4. FIRE ALARM PANEL: 3.5. REFER TO SPECIFICATIONS FOR ADDITIONAL RELATED, INFORMATION
- 4. INSTALLED FIRE ALARM SYSTEM SHALL BE ACCEPTANCE TESTED AS PER THE REQUIREMENTS OF NFPA 72, "INSPECTIONS, TESTING AND MAINTENANCE". INCLUDE THE COMPLETED "INSPECTION AND TESTING FORM" WITH THE OPERATION AND MAINTENANCE MANUALS THAT ARE ULTIMATELY PRESENTED TO THE OWNER.
- 5. PROVIDE FIRE ALARM SYSTEM INITIATION AND SIGNALING LOOP WIRING USING UL LISTED FIRE ALARM CABLE. SIZE CABLES APPROPRIATE FOR LOAD AND VOLTAGE DROP OF WIRING LOOPS. CABLING SHALL BE RUN WITHOUT RACEWAY WHERE CONCEALED IN WALLS OR ABOVE CEILINGS OR WHERE RUN IN EXPOSED ROOF STRUCTURE. PROVIDE RACEWAY WHERE RUN EXPOSED VERTICALLY ON WALLS OF SERVICE LEVEL TO MATCH RACEWAY UTILIZED FOR POWER
- 6. PROVIDE RED BOXES/COVERS FOR FIRE ALARM SYSTEM.
- 7. DORMITORY ROOMS: UPON A SMOKE DETECTOR LOCATED IN A DORM ROOM SENSING SMOKE, THE SIGNALING DEVICE IN THAT ROOM SHALL OPERATE (ONLY THAT DEVICE SHALL ALARM) AND CAUSE A TROUBLE SIGNAL AT THE FIRE ALARM SYSTEM. THE DORMITORY SMOKE DETECTORS SHALL OPERATE IN THE SAME/SIMILAR FASHION AS A SINGLE STATION DETECTOR EVÉN THOUGH IT IS A SYSTEM DETECTOR.
- 8. FACULTY RESIDENCES: UPON A SMOKE OR SMOKE/CO DETECTOR LOCATED IN A FACULTY RESIDENCE SENSING SMOKE OR CO, ALL SIGNALING DEVICES IN THAT RESIDENCE SHALL OPERATE AND CAUSE A TROUBLE SIGNAL AT THE BUILDING FIRE ALARM SYSTEM. THE FACULTY RESIDENCE SMOKE AND SMOKE/CO DETECTORS SHALL OPERATE IN THE SAME/SIMILAR FASHION AS MULTIPLE STATION DETECTORS EVEN THOUGH THEY ARE SYSTEM DETECTORS.

#### FIRE RISER DRAWING NOTES:

- F1 PROVIDE A 20A1P, 120VAC CIRCUIT TO THIS EQUIPMENT. PROVIDE A LOCK-ON CLIP FOR THE CIRCUIT BREAKER.
- F2 PROVIDE #4 AWG GROUND WIRE TO AN ELECTRICAL SYSTEM GROUNDING ELECTRODE.
- (F3) PROVIDE KEY BOX PER FIRE DEPARTMENT REQUIREMENTS AND LOCATE AS PER MUNICIPAL FIRE DEPARTMENT DIRECTION.
- F4) PROVIDE A REMOTE POWER SUPPLIES (NAC, SNAC, ETC.) AS NECESSARY TO SUPPORT POWERING OF ALARM SIGNALS THROUGHOUT THE FACILITY. THE REMOTE POWER SUPPLY IS NOT INDICATED ON PLANS; LOCATE IN A NON-PUBLIC SPACE AND INDICATE LOCATION ON SHOP DRAWINGS. PROVIDE
- F5 COORDINATE THE FINAL LOCATION AND QUANTITY OF SPRINKLER SYSTEM FLOW SWITCHES, TAMPER SWITCHES, ETC. WITH THE FINAL FIRE ALARM AND SPRINKLER SHOP DRAWINGS PRIOR TO INSTALLATION. COORDINATE CONNECTIONS WITH SPRINKLER SYSTEM CONTRACTOR.

SMOKE DETECTOR ABOVE WHERE PANEL IS LOCATED.

- (F6) PROVIDE CONNECTION TO TWO TELEPHONE LINES FOR PROPER OPERATION OF FIRE ALARM PANEL DIGITAL DIALER AS PRIMARY COMMUNICATION FOR TRANSMITTING OF ALARM CONDITIONS OFF-SITE TO EITHER CENTRALLY MANNED STATION OR TO THE MUNICIPAL FIRE DEPARTMENT.
- F7 PROVIDE OUTPUT MODULES TO SEND SIGNAL TO ELEVATOR TO INITIATE RECALL UPON ALARM SIGNAL FROM HEAT OR SMOKE DETECTORS IN ELEVATOR MACHINE ROOM, SHAFT OR ELEVATOR
- F8 PROVIDE OUTPUT MODULES TO SEND SIGNAL TO ELEVATOR SHUNT TRIP CIRCUIT BREAKER TO OPEN UPON SIGNAL FROM 135F FIXED TEMPERATURE HEAT DETECTOR AT TOP OF SHAFT.
- F9 COMBINATION SMOKE DETECTOR WITH 135F FIXED EMPERATURE HEAT DETECTOR AT THE TOP OF SHAFT.
- (F10) PROVIDE INPUT MODULE TO MONITOR KITCHEN HOOD FIRE PROTECTION SYSTEM AND SEND SIGNAL FOR ALARM TO TH FIRE ALARM SYSTEM UPON SENSING FIRE AND RELEASING
- F11) PROVIDE OUTPUT MODULES AS NECESSARY FOR SIGNAL TO UL924 RELAYS TO BRING EMERGENCY LIGHTING TO FULL OUTPUT UPON FIRE ALARM GOING INTO ALARM.

#### **ELECTRICAL LEGEND:**

SEE LUMINAIRE SCHEDULE FOR LUMINAIRE

OCCUPANCY SENSOR LIGHTING CONTROL DEVICE; REFER TO SCHEDULE DAYLIGHT SENSOR MANUAL SINGLE POLE LIGHTING SWITCH; 3 = 3 WAY, OC = OCCUPANCY SENSOR, PIR =

- PASSIVE INFRARED; DT = DUAL TECHNOLOGY; D = DIMMING, LV = LOW VOLTAGE, P = SWITCH WITH PILOT, K = KEYED SWITCH
- PHOTOELECTRIC CONTROL SENSOR
- TIMECLOCK CONTROLLER
- ELECTRICAL PANELBOARD
- ELECTRIC METER HOMERUN TO PANEL INDICATED
- BRANCH CIRCUIT OR FEEDER WIRING
- UNDERGROUND WIRING
- SINGLE RECEPTACLE OUTLET
- DUPLEX RECEPTACLE OUTLET
- DUPLEX RECEPTACLE OUTLET WITH 2 USB
- DOUBLE-DUPLEX (QUAD) RECEPTACLE OUTLET
- GROUND FAULT PROTECTION RECEPTACLE
- SPECIAL OUTLET (AS NOTED ON PLANS)
- RANGE HOOD CONNECTION
- JUNCTION BOX
- CONTROL RELAY
- LINE VOLTAGE THERMOSTAT, 'C' INDICATES
- MOTOR SWITCH
- SAFETY/DISCONNECT SWITCH; PROVIDE RATINGS AND FUSES AS PER SCHEDULES
- MAGNETIC MOTOR STARTER, FULL VOLTAGE, NON-REVERSING
- EQUIPMENT CONTROL PACKAGE; FURNISHED INTEGRAL TO THE EQUIPMENT
- MOTOR
- FIRE ALARM CONTROL PANEL
- FIRE ALARM ANNUNCIATOR PANEL
- FIRE FIGHTERS KEYBOX
- FIRE ALARM SYSTEM MANUAL PULLSTATION
- SPRINKLER SYSTEM FLOW SWITCH
- SPRINKLER SYSTEM TAMPER SWITCH
- SPRINKLER SYSTEM PRESSURE SWITCH
- FIRE ALARM SYSTEM INPUT MODULE FIRE ALARM SYSTEM OUTPUT MODULE
- PHOTOELECTRIC SMOKE DETECTOR; SB =
- = SINGLE STATION (NON-SYSTEM) SMOKE/CARBON MONOXIDE COMBO DETECTOR;

SOUNDER BASE, LF = LOW FREQUENCY, SS

- SB = SOUNDER BASE, LF = LOW FREQUENCY, SS = SINGLE STATION (NON-SYSTEM)
- FIRE ALARM SYSTEM HORN/STROBE WITH CANDELA RATING INDICATED
- FIRE ALARM SYSTEM STROBE VISUAL SIGNAL WITH CANDELA RATING INDICATED
- FIRE ALARM STROBE VISUAL SIGNAL, CEILING MOUNTED, SS = SINGLE STATION (NON-SYSTEM)
- DATA (LAN) DEVICE OUTLET, NUMBER INDICATES NUMBER OF CABLES; 1V1D = ONE
- VOICE, ONE DATA JACK/CABLE CATV (CABLE TELEVISION) DEVICE OUTLET
- CEILING MOUNTED DATA (LAN) WIRELESS ACCESS POINT, NUMBER INDICATES NUMBER
- ELEVATOR COMMUNICATIONS MASTER ANNUNCIATOR CONTROL PANEL
- ELEVATOR COMMUNICATIONS CALL STATION
- SECURITY CAMERA LOCATION, CEILING MOUNTED, UON
- ACCESS CONTROL SYSTEM CARD READER
- MONITOR POINT ACCESS POINT

#### **ELECTRICAL ABBREVIATIONS:**

OVERHEAD ELECTRICAL LINES DRAWINGS. AFF, AFG, AFR ABOVE FINISH FLOOR, GRADE, ROOF NIGHT LIGHTING LUMINAIRE, CONNECTED TO UNSWITCHED PORTION OF LIGHTING CIRCUIT

- WEATHERPROOF WITH COVER "CLOSED" FOR RECEPTACLES; NEMA 3R FOR ENCLOSURES
- WET LOCATION WITH COVER "OPEN" FOR RECEPTACLES; NEMA 4 FOR ENCLOSURES
- ABOVE COUNTER CEILING MOUNTED
- WALL MOUNTED
- **TYPICAL**
- NOT TO SCALE
- UNLESS OTHERWISE NOTED EXISTING, TO REMAIN
- REMOVE EXISTING
- REMOVE, RELOCATE
- RELOCATED
- MECHANICAL EQUIPMENT CONNECTION

BUILDING EQUIPMENT CONNECTION

#### **GENERAL NOTES:**

THESE GENERAL NOTES APPLY TO ALL ELECTRICAL PLAN

- 1. FOLLOW ALL APPLICABLE CODES AND USE GOOD ELECTRICAL CONSTRUCTION PRACTICES WHEN DETERMINING TYPES O WIRING METHODS AND SIZING OF CONDUCTORS AND CONDUIT. INSTALL ALL POWER, CONTROL AND SIGNAL WIRING USING METHODS AS FOLLOWS:
- 1.1. UNDERGROUND ELECTRIC SERVICE WIRING: INDIVIDUAL CONDUCTORS IN GALVANIZED STEEL RIGID METALLIC CONDUIT (RMC) AS PER THE REQUIREMENTS OF LIBERTY
- 1.2. UNDERGROUND WIRING OR BENEATH CONCRETE SLAB (NOT ELECTRICAL SERVICE WIRING): INDIVIDUAL CONDUCTORS IN SCHEDULE 40 PVC RIGID NON-METALLIC CONDUIT (RNC) FOR DIRECT BURIAL TRANSITION TO GALVANIZED STEEL RIGID METALLIC CONDUIT (RMC) WHERE CONDUIT RISES TO BE EXPOSED ABOVE GRADE OR CONCRETE SLAB, FROM A MINIMUM OF 24" BELOW FINISHED GRADE.
- 1.3. UNDERGROUND WIRING OR BENEATH ROAD WAY OR PARKING AREA: INDIVIDUAL CONDUCTORS IN SCHEDULE 80 PVC RIGID NON-METALLIC CONDUIT (RNC) FOR DIRECT BURIAL: TRANSITION TO GALVANIZED STEEL RIGID METALLIC CONDUIT (RMC) WHERE CONDUIT RISES TO BE EXPOSED ABOVE GRADE OR CONCRETE SLAB, FROM A MINIMUM OF 24" BELOW FINISHED GRADE.
- 1.4. EXPOSED. EXTERIOR LOCATIONS: INDIVIDUAL CONDUCTORS IN GALVANIZED STEEL, RIGID METALLIC CONDUIT (RMC); FINAL CONNECTIONS TO MOTORIZED (VIBRATING) EQUIPMENT SHALL BE LIQUID TIGHT FLEXIBLE METALLIC CONDUIT (LFMC), MAXIMUM 6' LENGTH
- 1.5. WIRING CONCEALED IN INACCESSIBLE WALLS AND CEILINGS: MULTI-CONDUCTOR TYPE NM (NON-METALLIC SHEATHED) AND TYPE SE (SERVICE ENTRANCE) CABLE.
- 1.6. CONCEALED WIRING ABOVE ACCESSIBLE CEILINGS: MULTI-CONDUCTOR TYPE NM (NON-METALLIC SHEATHED) AND TYPE SE (SERVICE ENTRANCE) CABLE.

1.7. EXPOSED BRANCH CIRCUITS (MECHANICAL ROOM, UTILITY

- SPACES): INDIVIDUAL CONDUCTORS IN ELECTRICAL METALLIC TUBING (EMT) WITH SET SCREW FITTINGS; FINAL CONNECTIONS TO MOTORIZED (VIBRATING) EQUIPMENT SHALL BE FLEXIBLE METALLIC CONDUIT (FMC), MAXIMUM 6' LENGTH
- 1.8. CONTRACTOR SHALL CONSULT WITH ENGINEER REGARDING QUESTIONS REGARDING WIRING METHODS PRIOR TO ROUGH-IN OF WIRING

2. MINIMUM CONDUCTOR SIZE SHALL BE 12 AWG. PROVIDE AN

INSULATED GROUND CONDUCTOR WITHIN ALL CABLES AND

- RACEWAYS. ALL CONDUCTORS SHALL BE COPPER, UNLESS OTHERWISE NOTED 3. CIRCUITS SHALL BE 20A1P, (2#12, 1#12G) 1/2"C. OR
- CABLE, UNLESS INDICATED OTHERWISE. 4. ALL WIRING SHALL BE ROUTED CONCEALED AND DEVICES SHALL BE FLUSH/RECESSED MOUNTED TO THE GREATEST EXTENT POSSIBLE. WIRING IN THE UTILITY SPACES SHALL BE PERMITTED TO BE EXPOSED WHERE NO WALL FINISH EXISTS. WIRING ROUTED EXPOSED ON VERTICAL SURFACES SHALL BE ROUTED VERTICALLY; HORIZONTAL WIRING SHALL BE ROUTED AT THE CEILING LEVEL OF THESE SPACES, NOT
- 5. MOUNT LIGHTING CONTROL SWITCHES 48" ABOVE FINISHED FLOOR, WITHIN 6" OF THE LATCH SIDE OF THE DOOR, UNLESS OTHERWISE INDICATED. "AC" INDICATES MOUNTING 8" ABOVE COUNTER BACK SPLASH, APPROXIMATELY 44" ABOVE FINISHED FLOOR.

ON THE WALLS.

- 6. EXIT SIGN LUMINAIRES SHALL BE CONNECTED TO THE LIFE SAFETY LIGHTING CIRCUIT SERVING THE AREA, AHEAD OF ANY SWITCHING OR AUTOMATIC CONTROLS.
- 7. ALL LIGHTING LAYOUTS SHALL BE COORDINATED WITH ARCHITECT'S REFLECTED CEILING PLANS AND EXACT LOCATION OF LUMINAIRES SHALL BE CHECKED AT CONSTRUCTION TIME AND PRIOR TO INSTALLATION WITH OTHER TRADE'S LATEST DRAWINGS AND EQUIPMENT LAYOUTS. COORDINATE LUMINAIRE TRIMS AND MOUNTING WITH CEILING CONSTRUCTION. FINAL LOCATION OF LUMINAIRES SHALL BE REASONABLY CONDUCIVE TO ACCESS BY THE OWNER FOR ROUTINE MAINTENANCE.
- 8. MOUNT RECEPTACLE DEVICES 18" ABOVE FINISHED FLOOR, UNLESS OTHERWISE NOTED. MOUNT RECEPTACLE DEVICES SUCH THAT THEY ARE ORIENTED SO THE GROUND IS IN THE "UP" POSITION. "AC" INDICATES MOUNTING 8" OVER COUNTER BACK SPLASH, APPROXIMATELY 44" ABOVE FINISHED FLOOR.
- 8.1. ALL RECEPTACLES SHALL BE TAMPER PROOF STYLE. 8.1. ENSURE RECEPTACLE PLACEMENT MEETS ALL DWELLING UNIT CODE REQUIREMENTS, INCLUDING MAXIMUM 12' ON
- 8.2. RECEPTACLE (GENERALLY DEVICES) PLACEMENT ON
- BASEBOARD HEAT.
- 9.1. BASIS OF DESIGN PRODUCT IS 3M FIRE BARRIER MOLDABLE PUTTY PADS MPP+. PROVIDE A SUBMITTAL PRODUCT INFORMATION FOR REVIEW AND APPROVAL.
- ELECTRICAL BOXES, CABLE BOXES, FIRE SAFETY SYSTEM BOXES, ETC. 11. SMOKE DETECTORS AND CARBON MONOXIDE DETECTORS TO
- DIFFUSER OR PADDLE FAN. THE EQUIPMENT OR IS INDICATED IN THE EQUIPMENT WIRING DIAGRAM AND EQUIPMENT SCHEDULE. REFER TO

FOR CONNECTIONS TO CONTROL DEVICES.

# VERMONT INTEGRATED ARCHITECTURE, PC

ANDREA MURRAY, AIA, NCARB, LEED AP andrea@vermontintegratedarchitecture.com

ASHAR NELSON, AIA, LEED AP

ashar@vermontintegratedarchitecture.com

P.O. Box 862 Middlebury, VT 05753 802.989.7249

CIVIL ENGINEER Kevin Warden, P.E. Engineering Ventures kevinw@engineeringventures>com 802.863.6225

STRUCTURAL ENGINEER Bob Neeld, P.E, President Engineering Ventures bobn@engineeringventures.com 802.863.6225

MECH./PLUMBING ENGINEER Daniel Dupras, P.E. Engineering Services of Vermont, LLC daniel.dupras@esvtlc.com 802.855.8091

ELECTRICAL ENGINEER

CLAUS BARTENSTEIN, P.E., LEED-AP Engineering Services of Vermont, LLC claus.bartenstein@esvtllc.com 802.855.8091

CONSTRUCTION MANAGER NAMF & TITLF ReArch Company, Inc.

DATE ISSUED: 05/15/2023

EMAIL HERE

802.863.8727

Drawn: ESVT Checked: CPB REVISIONS:

CENTER SPACING

- WALLS COMMON BETWEEN DORM ROOMS SHALL BE LOCATED IN SEPARATE WALL CAVITY FROM THE NEIGHBORING ROOM. 8.3. DO NOT LOCATE ANY RECEPTACLES ABOVE ELECTRIC
- 9. PROVIDE MEMBRANE PROTECTION FOR ALL DEVICE BOXES PENETRATING FIRE RATED WALLS.
- 10. AIR AND VAPOR TIGHT BOXES SHALL BE USED AT EXTERIOR WALLS AND CEILINGS, BELOW ATTIC SPACES, AND ADJACENT TO UNCONDITIONED SPACES. THIS INCLUDES ALL
- MAINTAIN A MINIMUM 3'-0" SEPARATION FROM ANY HVAC 12. WHERE MECHANICAL EQUIPMENT IS INDICATED ON PLAN WITHOUT LOCAL DISCONNECT, EITHER IT IS FURNISHED WITH

MECHANICAL EQUIPMENT SCHEDULE AND WIRING DIAGRAMS

## PERMIT SET 05/15/2023

## KILTON/WELCH **DORMITORIES**

Main Street Meriden, NH 03770

ELECTRICAL NOTES, LEGEND, **DETAILS** 

#### **ELECTRICAL ALTERNATES**

REFER TO SPECIFICATION SECTION 26 0010, ELECTRICAL GENERAL PROVISIONS, FOR ALTERNATES THAT AFFECT THE ELECTRICAL WORK INDICATED ON THESE DOCUMENTS.

#### **GENERAL NOTES:**

REFER TO GENERAL NOTES ON DRAWING E1 WHICH APPLY TO THIS DRAWING AS WELL AS ANY NOTES WHICH FOLLOW.

1. REFER TO CIVIL DRAWINGS FOR LIGHT POLE BASE DETAIL.

- 2. ROUTING OF UNDERGROUND ELECTRICAL ON THIS PLAN IS TO SHOW GENERAL ROUTING. REFER TO CIVIL DRAWINGS FOR ACTUAL ROUTING THROUGH THE SITE COORDINATED WITH OTHER TRADES AND SITE FEATURES.
- 3. INSTALLATION OF RACEWAYS AND EQUIPMENT FOR LIBERTY UNDERGROUND PRIMARY LINE EXTENSIONS SHALL BE INSTALLED AS PER LIBERTY REQUIREMENTS, INCLUDING CONCRETE ENCASEMENT OF PRIMARY WIRING RACEWAYS.

#### **GENERAL DEMOLITION NOTES:**

- 1. THESE DEMOLITION NOTES APPLY TO ALL DEMOLITION REQUIRED OF THIS PROJECT AND AS GENERALLY INDICATED ON THE DEMOLITION AND CONSTRUCTION DRAWINGS.
- 2. ITEMS INDICATED AS EXISTING TO REMAIN ARE SHOWN FOR INFORMATIONAL PURPOSES, ONLY.
- 3. DEMOLITION AND RELOCATION WORK INDICATED ON THE DRAWINGS IS BASED UPON THE BEST AVAILABLE INFORMATION. THE ELECTRICAL CONTRACTOR SHALL WALK THROUGH THE DEMOLITION AREAS TO IDENTIFY THE EXACT LOCATION AND ELECTRICAL WORK INVOLVED PRIOR TO BIDDING. MAJOR DEVIATIONS FOUND SHALL BE REPORTED TO THE ENGINEER.
- 4. REMOVE ALL LUMINAIRES, DEVICES, WIRING AND CONDUIT ON THE WALLS AND CEILINGS TO BE DEMOLISHED. WIRING AND CONDUIT SHALL BE REMOVED TO THE LAST LIVE OUTLET TO REMAIN OR ALL THE WAY TO THE SOURCE, AS NOTED. REWORK AND EXTEND EXISTING CIRCUIT WIRING AND CONDUITS AS NECESSARY TO MAINTAIN POWER TO EXISTING DEVICES AND EQUIPMENT TO REMAIN.
- 5. THE ELECTRICAL CONTRACTOR SHALL REVIEW MATERIAL AND EQUIPMENT TO BE SALVAGED AT THE BEGINNING OF THE PROJECT WITH THE OWNER AND GENERAL CONTRACTOR. THE MATERIAL AND EQUIPMENT MAY INCLUDE FIRE ALARM DEVICES, SECURITY SYSTEM DEVICES, ETC.. IN GENERAL, ALL MATERIAL NOT REQUESTED TO BE SALVAGED BY TH OWNER SHALL BECOME THE PROPERTY OF THE ELECTRICAL CONTRACTOR AND SHALL BE REMOVED FROM THE SITE. SHALL BE THE ELECTRICAL CONTRACTOR'S RESPONSIBILITY TO PROVIDE FOR THE PROPER ENVIRONMENTAL DISPOSAL OF THESE MATERIALS.
- 6. REWORKING EXISTING CIRCUITS, CONNECTING TO EXISTING CIRCUITS OR EXTENDING EXISTING CIRCUITS SHALL BE THE ELECTRICAL CONTRACTOR'S RESPONSIBILITY TO FIELD VERIFY. ALL PANELBOARDS, SWITCHES, RECEPTACLES, DEVICES, ETC. TO BE USED, WHETHER SHOWN OR NOT SHOWN, SHALL BE TO THE DISCRETION OF THE ELECTRICAL CONTRACTOR AND HIS RESPONSIBILITY TO FIELD VERIFY. MAJOR DEVIATIONS SHALL BE REPORTED TO THE ENGINEER.

#### **DEMOLITION DRAWING NOTES:**

1 DISCONNECT AND REMOVE ANY FEEDER WIRING TO THIS STRUCTURE BACK TO SOURCE TO ALLOW FOR STRUCTURE DEMOLITION.

2 DISCONNECT AND REMOVE POLE LUMINAIRE AND RETAIN FOR REUSE. REMOVE WIRING BACK TO SOURCE.

#### **DRAWING NOTES:**

THESE DRAWING NOTES APPLY TO THIS DRAWING, ONLY, 1) TO EXTERIOR LIGHTING CONTROLS IN KILTON.


2 RELOCATED POLE LUMINAIRE.

3 PROVIDE NEW FEEDER TO EXISTING PANELBOARD IN RELOCATED GARAGE. PROVIDE GROUND ROD ELECTRODE WITH #4CU GROUNDING ELECTRODE CONDUCTOR FROM EXISTING

4 LOCATE GENERATOR ON A 6" THICK CONCRETE PAD, 4" LARGER THAN GENERATOR FOOT PRINT, IN ALL DIRECTIONS.

5 PROVIDE CIRCUITS FROM PANEL PK IN KILTON DORM FOR GENERATOR BLOCK/OIL HEATER, ALTERNATOR HEATER, BATTERY CHARGER AND RECEPTACLE. ALL CIRCUIT WIRING TO BE (2#8, 1#10G) 1"C.

#### PAVED AREAS



NOTES:

1. DETAIL IS TYPICAL FOR ALL WIRING THAT IS NOT ELECTRICAL SERVICE POWER WIRING.

- 2. COMPLY WITH OSHA TRENCH PROTECTION REQUIREMENTS.
- 3. PROVIDE CONDUIT SPACERS/SADDLES EVERY 6 FEET.

  4. BURIAL DEPTH IS SHOWN FOR DIRECT BURIAL PVC RIGID NON-METALLIC CONDUIT. WHERE SPECIFIED BURIAL DEPTH IS NOT POSSIBLE, UTILIZE GALVANIZED STEEL RIGID METALLIC CONDUIT. NOTIFY ENGINEER PRIOR TO ANY CHANGE OF
- WIRING METHODS. 5. DETAIL IS TYPICAL INSTALLATION; PROVIDE QUANTITY OF CONDUITS AS REQUIRED FOR THE INSTALLATION AND AS DIRECTED IN THE PLANS AND DETAILS.

TYPICAL ELECTRICAL **DUCTBANK DETAIL** 

# **VERMONT INTEGRATED** ARCHITECTURE, PC

ANDREA MURRAY, AIA, NCARB, LEED AP andrea@vermontintegratedarchitecture.com

ASHAR NELSON, AIA, LEED AP ashar@vermontintegratedarchitecture.com

P.O. Box 862 Middlebury, VT 05753 802.989.7249

CIVIL ENGINEER Kevin Warden, P.E. Engineering Ventures kevinw@engineeringventures>com 802.863.6225

STRUCTURAL ENGINEER

Bob Neeld, P.E, President Engineering Ventures bobn@engineeringventures.com 802.863.6225

MECH./PLUMBING ENGINEER Daniel Dupras, P.E.

Engineering Services of Vermont, LLC daniel.dupras@esvtlc.com 802.855.8091

#### ELECTRICAL ENGINEER

CLAUS BARTENSTEIN, P.E., LEED-AP Engineering Services of Vermont, LLC claus.bartenstein@esvtllc.com 802.855.8091

CONSTRUCTION MANAGER NAME & TITLE ReArch Company, Inc. EMAIL HERE

DATE ISSUED: 05/15/2023 Drawn: ESVT Checked: CPB

**REVISIONS:** 

802.863.8727



PERMIT SET 05/15/2023

#### KUA KILTON/WELCH **DORMITORIES**

Main Street Meriden, NH 03770

ELECTRICAL SITE PLAN