

COBY



TOWN OF PLAINFIELD, NEW HAMPSHIRE
110 Main Street
Plainfield, NH 03781

PO BOX 380, Meriden NH 03770
e-mail: plainfield.ta@plainfieldnh.org
www.plainfieldnh.org

Telephone (603) 469-3201
facsimile 3642

Monday, January 08, 2018

Hansen Bridge
1252 County Road
New London, NH 03257

Re: Plainfield Bridges 2018 Camp Road (177/096), Ladieu or Houser Lane (131/152)

Mike:

Enclosed you will find a check for \$102,845 representing the 50% deposit for each of the above bridge replacements. Per our signed agreements (copies attached), Camp Road to cost \$100,000 (\$50,000 deposit), Ladieu to cost \$105,690 (deposit \$52,845). The town hopes to reduce the Ladieu project by \$5,915 if we remove the bridge ourselves, leaving a balance due on Camp of \$50,000 and Ladieu of \$44,085.

As we have discussed, it is critical that once we start that we complete the Camp Road Bridge no later than **Monday August 27th** (just prior to Plainfield School start up). The Ladieu project may run later, but again should be done by **Monday October 1st** to insure that we can remove the temporary bridge and do the necessary site work and seeding prior to the end of the growing season.

Call or stop in with any questions. We look forward to working closely with you to complete these two projects during the summer of 2018. As we have discussed, in order to keep costs down, the resources of the Plainfield Highway Department will be available to you in any way that you find necessary.

Regards,


Stephen Halleran



1252 County Road, New London, NH 03257
603-526-4049 / 603-526-4205
hansenbridge@tds.net

BRIDGE SUPERSTRUCTURE
REPLACEMENT ESTIMATE

January 1, 2018

CLIENT:
Town Of Plainfield
Attn: Steve Halleran (603) 469-3201

RE: Bridge Construction , Ladieu Road Bridge over Bloods Brook

Payment: Prior written approval in the form of a change order will be required before any additional work can be executed. An additional work price outline and change order form is provided for your convenience upon request.

Payment Schedule : #1 \$52,845.00 deposit prior to construction
#2 \$52,845.00 due after bridge is complete.

Description: Install a 29'-2" span x 16'-0" wide glue laminated timber bridge superstructure on existing abutments. Abutment repair and modifications by others. (total dead load wt = 24,000 lbs) Installation of TL-2 crash rated timber bridge rail system on bridge. Approach rail and attachment if required by others.

BRIDGE ITEMS

Description	Estimated Qty	Unit	
Timber Glue Laminated Beams	1	UNIT	
		TOTAL	\$105,690.00

- Price Includes \$12,437.00 for crash rated TL-2 bridge rail.
- Price Includes \$18,000.00 for 50' x 12'-6" wide temporary bridge on precast abutments. Temporary detour and road installation and removal by others. Price includes the installation and removal of temporary bridge.
- Price Includes NHDOT DOT Form 4 and NH PE stamped drawings HS-25 load rating.
- Price Included \$5,915.00 for existing bridge removal. Existing abutment seat modifications if required by others.

Acceptance of above contract by owner, Mr.

Date

Signature

[Handwritten Signature] 11/15/18 *[Handwritten Signature]*

Steve Halleran
TA

Thank you,
Hansen Construction
Michael Hansen, President

pd 52,845 Deposit 11/11/18